

SD76-SH-0092
VOLUME II
PART 2

SHUTTLE PAYLOAD INTERFACE VERIFICATION
EQUIPMENT STUDY
VOLUME II TECHNICAL DOCUMENT -
PART 2 APPENDICES

APRIL 1976

NASA CONTRACT: NAS9-14000 CCA 140 REV. 1

PREPARED BY:
SHUTTLE PAYLOAD
INTERFACE PROJECTS GROUP

APPROVED BY:

H. E. Emigh

H. E. EMIGH

DIRECTOR

STS/PAYLOAD INTEGRATION

(NASA-CF-147667) SHUTTLE PAYLOAD INTERFACE
VERIFICATION EQUIPMENT STUDY. VOLUME 2:
TECHNICAL DOCUMENT. PART 2: APPENDICES
(Rockwell International Corp., Downey,
Calif.) 171 p HC \$6.75

N76-22263

CSCI 22E G3/18

Unclas

25352

MAY 1976

RECEIVED


NASA STI FACILITY
INPUT BRANCH



Rockwell International

Space Division

SD76-SH-0092
VOLUME II
PART 2



SHUTTLE PAYLOAD INTERFACE VERIFICATION
EQUIPMENT STUDY
VOLUME II TECHNICAL DOCUMENT -
PART 2 APPENDICES

APRIL 1976

NASA CONTRACT: NAS9-14000 CCA 140 REV. 1

PREPARED BY:
SHUTTLE PAYLOAD
INTERFACE PROJECTS GROUP

APPROVED BY:

H. E. EMIGH

DIRECTOR

STS/PAYLOAD INTEGRATION



Rockwell International

Space Division



FOREWORD

This document is a contractual requirement of NAS9-14000, CCA 140 Revision 1 and is provided in response to the contract. The study was conducted by the Space Division of Rockwell International for the Johnson Space Center of the National Aeronautics and Space Administration. It is published in four volumes:

- | | |
|----------|--|
| Vol. I | Executive Summary |
| Vol. II | Technical Document - Part 1
Technical Appendices - Part 2 |
| Vol. III | Specification Data |
| Vol. IV | Project Plans |

TECHNICAL REPORT INDEX/ABSTRACT

ACCESSION NUMBER				DOCUMENT SECURITY CLASSIFICATION		Unclassified	
TITLE OF DOCUMENT						LIBRARY USE ONLY	
Shuttle Payload Interface Verification Equipment(IVE) Study							
AUTHOR(S)							
CODE	ORIGINATING AGENCY AND OTHER SOURCES				DOCUMENT NUMBER		
	Rockwell International Corporation Space Division, Downey Calif.				SD76-SH-0092		
PUBLICATION DATE			CONTRACT NUMBER				
April 1, 1976			NAS9-14000 CCA 140 Rev. 1				
DESCRIPTIVE TERMS							
Shuttle		Preliminary Design		Data Management			
Payloads		Operators Console		Computer			
Spacelab		Mission Station		Heat Exchanger			
P/L Interface		On-Orbit Station		Development Plans			
P/L Interface Verif.		Payload Station		Schedules			
Avionics		Electrical Power					
Payload Integration		Communications					

ABSTRACT

Single and mixed payloads must be integrated into the Shuttle Orbiter within the 160 hour turnaround requirement for the Shuttle system. In order to accomplish this integration process some off-line integration capability is required. This report is a preliminary design analysis of a "stand alone" (no facility GSE support required) payload integration device (IVE) capable of verifying payload compatibility in form, fit and function with the Shuttle Orbiter prior to on-line payload/Orbiter operations. The IVE is a high fidelity replica of the Orbiter payload accommodations capable of supporting payload functional check-out and mission simulation. A top level payload integration analysis developed detailed functional flow block diagrams of the payload integration process for the broad spectrum of P/L's and identified degree of Orbiter data required by the payload user and potential applications of the IVE.

This work was performed for Johnson Space Center of the National Aeronautics and Space Administration under contract NAS9-14000 CCA 140 Rev. 1.

PRECEDING PAGE BLANK NOT FILMED



TABLE OF CONTENTS

Appendices		Page
A	Interface Verification Equipment Hardware. . . Utilization List (HUL)	A-1
B	Horizontal IVE In-Field Assembly Procedure . .	B-1
C	Payload Integration Baseline Functional. . . . Flow Block Diagrams and Options	C-1

PRECEDING PAGE BLANK NOT FILMED



APPENDIX A

INTERFACE VERIFICATION EQUIPMENT HARDWARE UTILIZATION LIST (HUL)



IVE
HARDWARE UTILIZATION LIST
INDEX


<u>HUL I.D.</u>	<u>ITEM</u>	<u>WBS</u>
1001-00-000	MID-BODY STRUCTURE	1.2.1.1.1.a
2101-00-000	MS/PS SUPPORT MODULE	1.2.1.1.1.b
2102-00-000	X _O 576 BULKHEAD	1.2.1.1.1.b
2103-00-000	PAYLOAD WIRE TRAY	1.2.1.1.1.g
2004-00-000	X _O 679.5 POWER PANEL	1.2.1.1.1.f
2005-00-000	PREFLIGHT UMBILICAL	1.2.1.1.1.h
2106-00-000	X _O 1307 CROSS SUPPORT	1.2.3.1.1.n
2007-00-000	X _O 576 AVIONICS HARNESS SUPPORT	1.2.1.1.1.b
2108-00-000	MISSION SPECIALIST SECONDARY STRUCTURE	1.2.1.2.2.a.1
2109-00-000	PAYLOAD SPECIALIST SECONDARY STRUCTURE	1.2.1.2.2.a.3
2110-00-000	ON-ORBIT STATION SECONDARY STRUCTURE	1.2.1.2.2.a.2
3001-00-000	OPERATOR'S CONSOLE	1.2.1.2.1
3002-00-000	DC POWER SET	1.2.1.2.3
3004-00-000	AFT FLIGHT DECK SET	1.2.1.2.2
3005-00-000	DELETED	
3006-00-000	DELETED	
3007-00-000	DELETED	
3108-00-000	CABLE SET	1.2.1.2.4
3109-00-000	DELETED - SEE 3108-00-000	
3110-00-000	DELETED - SEE 3108-00-000	
4101-00-000	X _O 576 AIRLOCK INTERFACE	1.2.3.1.1.g
4102-00-000	X _O 660 TUNNEL INTERFACE	1.2.3.1.1.h
4003-00-000	P/L PRIMARY LONGERON FITTING, NON- DEPLOYABLE	1.2.1.1.1.c 1.2.3.1.1.a
4104-00-000	AUXILIARY KEEL FITTING	1.2.1.1.1.e 1.2.3.1.1.c
4105-00-000	P/L UPPER CLEARANCE GAGE	1.2.3.1.1.i



IVE
HARDWARE UTILIZATION LIST
INDEX
(CONT)


<u>HUL I.D.</u>	<u>ITEM</u>	<u>WBS</u>
4106-00-000	LOWER CLEARANCE GAGE	1.2.3.1.1.j
4107-00-000	OMS DELTA V ENVELOPE	1.2.3.1.1.k
4108-00-000	FLOODLIGHT X ₀ 576 BULKHEAD	1.2.3.3.1.a
4009-00-000	X ₀ 576 PAYLOAD SERVICE PANEL	1.2.1.2.2.a.5 1.2.3.3.1.f
4110-00-000	ENVIRONMENTAL CONTROL UNIT SET	1.2.3.2.1.a
4111-00-000	(DELETED)	
4012-00-000	HOISTING	1.5.1
4013-00-000	(DELETED)	
4014-00-000	TV, X ₀ 576 BULKHEAD	1.2.3.3.1.c
4115-00-000	TV X ₀ 1307 BULKHEAD	1.2.3.3.1.c
4116-00-000	PAYLOAD BAY LINER	1.2.3.1.1.i
4017-00-000	PREFLIGHT UMBILICAL ELECTRICAL PANEL	1.2.3.3.1.d
4018-00-000	PREFLIGHT UMBILICAL FLUID PANEL	1.2.3.2.1.d
4019-00-000	PAYLOAD BAY FLOODLIGHT	1.2.3.3.1.b
4120-00-000	X ₀ 1307 BULKHEAD	1.2.1.1.1.b
4121-00-000	X ₀ 1307 P/L OXIDIZER/FUEL PANELS	1.2.3.2.1.b
4122-00-000	PAYLOAD MASS SIMULATOR	1.5.1
4123-00-000	(DELETED)	
4124-00-000	X ₀ 1307 ELECTRICAL SERVICE PANEL	1.2.3.3.1.e
4125-00-000	(DELETED)	
4126-00-000	STABILIZING LONGERON FITTING, NON- DEPLOYABLE PAYLOAD	1.2.1.1.1.d 1.2.3.1.1.b
4127-00-000	CABLE SETS	1.2.3.3.1.g
4128-00-000	T-O UMBILICAL PROVISIONS	1.2.3.1.1.m
4129-00-000	T-O UMBILICAL FLUID I/F ASSEMBLY	1.2.3.2.1.c

IVE
HARDWARE UTILIZATION LIST
IDENTIFICATION CODE



<u>CATEGORY</u>	<u>CODE</u>
PRIMARY STRUCTURE	1XXX
SECONDARY STRUCTURE	2XXX
ELECTRONICS	3XXX
OPTIONAL EQUIPMENT	4XXX

SAMPLE:



IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.	WEIGHT / ITEM	MATERIAL / SPEC.	DRAWING NUMBER	TEST REQMTS.	DEVELOPMENT	MANUFACTURE	REVENUE	SUB-SYSTEM	SYSTEM	SPARES
						M • MAKE	H • HORIZONTAL	X • TEST REQUIRED										
						B • BUY	V • VERTICAL	I • QUANTITY FOR TEST										
						O • OFF THE SHELF	C • COMMON											
PRIMARY STRUCTURE NOMENCLATURE						DESCRIPTION												
MODULE		ASSEMBLY		ITEM														
01	1.2.1.1.1.0	M	C	3	1001-00-000	MID-BODY SECTION			110 X 210 X 240	16882	(3) • 50,648							
02		M	C	2	1001-01-000		VERTICAL PANEL ASSY.		12 X 118 X 240 WELDED ASSY.	6923								
03		M	C	2	1001-01-001			LONGERON - BOX	6 X 10 X 0.50 X 240 TUBE	947	CARBON STEEL ASTM-A500							
04		M	C	2	1001-01-002			STIFFENER - ANGLE	0.50 X 9 1/2 X 240 ANGLE	439	CARBON STEEL ASTM-A36							
05		M	C	2	1001-01-003			CLEVIS RAIL	2 1/2 X 3 1/2 X 240 BAR	310	1010 STEEL							
06		M	C	2	1001-01-004			BRIDGE RAIL	2 1/2 X 3 1/2 X 240 BAR	291	1010 STEEL							
07		M	C	3	1001-01-005			POST - END & CENTER	6 X 6 X .3125 X 95 TUBE	213	CARBON STEEL ASTM-A500B							
08		M	C	4	1001-01-006			DIAGONAL	4 X 6 X .250 X 103 TUBE	132								
09		M	C	2	1001-01-007			LOWER CORD	6 X 10 X .375 X 240 TUBE	736	CARBON STEEL ASTM-A500B							
10		M	C	4	1001-01-008			GUSSET - END POST	13 X 21 X .50 PLATE	38.6	ASTM-A-572B GRADE 50							
11		M	C	2	1001-01-009			GUSSET - CENTER (UP)	9 X 11 X .250 PLATE	7								
12		M	C	2	1001-01-010			GUSSET - CENTER (DOWN)	9 X 13 X .250 PLATE	8.2								
13		M	C	4	1001-01-011			GUSSET - DIAGONAL	9 X 11 X .250 PLATE	7								
14		M	C	2	1001-01-012			GUSSET - CORNER	11 X 13 X .50 PLATE	20.2	ASTM-A-572B GRADE 50							
15		M	C	4	1001-01-013			GUSSET - HORIZONTAL	6 X 6 X .375 PLATE	3.8								
16		B	C	35	1001-01-014		VERTICAL PANEL ASSY.	BOLT & NUT	.75 DIA X 3 1/2 LONG	.75								
17		M	C	3	1001-00-001			CROSS BEAM	10 X 5 3/4 W.F X 188 (I)	391	ASTM-A36							
18		M	C	2	1001-00-002			KEEL BEAM	10 X 5 3/4 W.F X 115 (I)	239	ASTM-A36							
19		M	C	2	1001-00-003			TIE ROD	1 1/2 DIA. X 290	177								
20		M	C	6	1001-00-004			KNEE BRACE	4 X 6 X .250 X 71 TUBE	91	ASTM-A500B							
21		M	C	6	1001-00-005			FOOT - KNEE BRACE	6 X 13 X .375 PLATE	4	ASTM-A572B							
22		M	C	3	1001-00-006			HEAD - KNEE BRACE	5 X 7 X .375 X 10 TUBE	23	ASTM-A500B							
23		M	C	2	1001-00-007			KEEL LONGERON	2 X 3 X 2 1/2 X .250 X 240 TUBE	138.6	ASTM-A36							
24		M	C	6	1001-00-008			CLIP - C' BEAM	7 X 7 X .375 PLATE	5.2								
25	1.2.1.1.1.0	M	C	4	1001-00-009			CLIP - R' BEAM	3 1/2 X 7 X .375 PLATE	2.6	ASTM-A36							
26	1.2.1.1.1.0	B	H	4	1001-00-010			BOLT - LEVELING	1 3/4 DIA. X 14 (UNC-2 THD)	9.5	ASTM-A325							
27	1.2.1.1.1.0	B	C	108	1001-00-011			BOLT - C' BEAM	1/2 DIA X 1 1/2" LONG	.2								
28	1.2.1.1.1.0	B	C	12	1001-00-012			BOLT - KNEE BRACE	3/4 DIA X 7" LONG	1.2								
29	1.2.1.1.1.0	B	C	4	1001-00-013	MID-BODY SECTION		NUT - LEVELING	1 3/4 DIA. (UNC-2 THRD)									

ORIGINAL PAGE IS
OF POOR QUALITY

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	VIBS NUMBER	SOURCE	CONFIGURATION	UNITS	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.	WEIGHT	MATERIAL/SPEC.	DRAWING OR REQUIREMENT SPEC. NUMBER	TEST REQMTS.				
						M - MAKE	H - HORIZONTAL	X - TEST REQUIRED				DEVELOPMENT	QUALIFICATION	ACCEPTANCE	REVIEWING	SUB-SYSTEM
						B - BUY	V - VERTICAL	I - QUANTITY FOR TEST				SYSTEM	SHARES			
						SECONDARY STRUCTURE NOMENCLATURE										
						MODULE	ASSEMBLY	ITEM	DESCRIPTION							
121.116	M	H	1	2101-00-000	M/S/PS SUPPORT MODULE				3945							
	M	H	2	2101-01-000			SUPPORT ASSEMBLY		78X88X120 WELDED ASSEMBLY	1739						
	M	H	4	2101-01-001				POST-VERTICAL	3X3X.188 X 120 TUBE	69						
	M	H	4	2101-01-002				CROSS TIE - LONGITUDINAL	3X3X.188 X 88 TUBE	50						
	M	H	4	2101-01-003				CROSS TIE - TRANSVERSE	3X3X.188 X 78 TUBE	45						
	M	H	4	2101-01-004				DIAGONAL - LONGITUDINAL	3X3X.188 X 122 TUBE	70						
	M	H	4	2101-01-005				DIAGONAL - TRANSVERSE	3X3X.188 X 120 TUBE	69						
	M	H	8	2101-01-006				PLATE - STAND	6X6X.50	56						
	M	H	8	2101-01-007				PLATE - FLOOR	8X8X.50	10						
	M	H	8	2101-01-008				BOLT - ADJUSTING	1" DIA X 8 TPI X 9" LONG	2						
	M	H	8	2101-01-009				NUT - LOCK	1" DIA X 8 TPI	2						
	M	H	2	2101-01-010				DECK SUPPORT	3X3X.188 X 72 TUBE	41						
	M	H	1	2101-01-011			SUPPORT ASSEMBLY	DECK PLATE	78X88X.125 PLATE DIAGONAL PATTERN	293						
	M	H	1	2101-00-001				DECK PLATE	28 X 88 X .125 PLATE DIAGONAL PATTERN	105						
	M	H	1	2101-03-000			LADDER ASSEMBLY		19X26X154 WELDED ASSY.	209						
	M	H	2	2101-03-001				HANDRAIL	1 1/2 O.D.(NOM) X .145 X 168 PIPE	38						
	M	H	2	2101-03-002				VERTICAL SUPPORT	2X1X.188 X 120 CHANNEL	23						
	M	H	8	2101-03-003				CROSS TIE	1 1/2 O.D.(NOM) X .145 X 15 PIPE	4						
	M	H	9	2101-03-004				STEP	2X1X.188 X 84 CHANNEL	5						
	M	H	6	2101-03-005			LADDER ASSEMBLY	BRACKET	2X2X.125 X 12 ANGLE	14						
	M	H	2	2101-04-000			HANDRAIL ASSY- SIDE		33X74 WELDED ASSY.	70						
	M	H	4	2101-04-001				POST	1 1/2 O.D.(NOM) X .145 X 32 PIPE	7						
	M	H	1	2101-04-002				HANDRAIL	1 1/2 O.D.(NOM) X .145 X 74 PIPE	17						
	M	H	3	2101-04-003				CROSS TIE	1 O.D.(NOM) X .133 X 23 PIPE	3116						
	O	H	4	2101-04-004			HANDRAIL ASSY- SIDE	FLOOR FLANGE	1 X 5 X 6	4						
	M	H	2	2101-05-000			HANDRAIL ASSY- FRONT		1 1/2 O.D.(NOM) X .145 X 32 PIPE	69						
	M	H	3	2101-05-001				POST	1 1/2 O.D.(NOM) X .145 X 83 PIPE	7						
	M	H	1	2101-05-002				HANDRAIL	1 O.D.(NOM) X .133 X 27 PIPE	4						
	M	H	3	2101-05-003				CROSS TIE	1 X 5 X 6	4						
	O	H	3	2101-05-004			HANDRAIL ASSY- FRONT	FLOOR FLANGE	1 X 5 X 6	4						
	O	H	4	2101-00-002	M/S/PS SUPPORT MODULE			ELC - SIDE OUTLET	3X3X3	15						

DELETED

DELETED FACILITY PROVIDED

OF POOR QUALITY

DELETED FACILITY PROWARD

ORIGINAL PAGE IS
OF POOR QUALITY

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SECONDARY STRUCTURE NOMENCLATURE			DESCRIPTION	WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQMT'S																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
						MODULE	ASSEMBLY	ITEM					TEST REQMT'S	DEVELOPMENT	QUALIFICATION	ACCEPTANCE	RECEIVING	SUB-SYSTEM	SYSTEM	SPARES																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
																					M - MAKE	H - HORIZONTAL	V - VERTICAL	X - TEST REQUIRED	I - QUANTITY FOR TEST																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
																										B - BUY	C - COMMON																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.		WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQMTS.								
					M: MAKE	H: HORIZONTAL	X: TEST REQUIRED					DEVELOPMENT	QUALIFICATION	ACCEPTANCE	REVIEWING	SUB-SYSTEM	SYSTEM SPARES			
					B: BUY	V: VERTICAL	I: QUANTITY FOR TEST													
					O: OFF THE SHELF	C: COMMON														
					SECONDARY STRUCTURE NOMENCLATURE			DESCRIPTION												
					MODULE	ASSEMBLY	ITEM													
12.11.1.9		M H	2	2103-00-000	PAYLOAD WIRE TRAY				66											
		M H	1	2103-01-000		TRAY ASSY			66.2											
		M H	4	2103-01-001			ANGLE - DIVIDER	3/4 X 3 X .040 X 240 ANGLE	3.0	AL SHEET										
		M H	2	2103-01-002			COVER - TRAY	15 X 120 X .050 SHEET	9	AL SHEET										
		M H	1	2103-01-003		TRAY ASSY	WIRE TRAY CHANNEL	22 X 240 X .060 SHEET	32	AL SHEET										
		M H	6	2103-01-004	PAYLOAD WIRE TRAY		BRACKET ATTACH	1 1/2 X 2 X .188 X .3 ANGLE	3	AL EXTR.										
12.11.1.F		M C	1	2004-00-000	Xo 6785 POWER PANEL				4.4											
		M C	1	2004-01-000		POWER PANEL ASSY		5 X 13 X 13 BOLT ON ASSY	1.6											
		M C	2	2004-01-001			BRACKET	5 X 11 X .060 SHEET	.3	AL SHEET										
		M C	1	2004-01-002		POWER PANEL ASSY	PANEL	13 X 13 X .060 SHEET	1.0	AL SHEET										
		B C	2	2004-01-003	Xo 6785 POWER PANEL		CONNECTOR - FEMALE	SHELL # 36 - FOUR "O" CASE WIDE	.6											
12.11.1.6		M C	1	2005-00-000	PREFLIGHT UMBILICAL				.780											
		M C	1	2005-01-000		UMBILICAL PANEL ASSY			6.6											
		M C	1	2005-01-001			PANEL - OUTBOARD	22 X 25 X .060 SHEET - 1 (1111)	1.3	AL SHEET										
		M C	1	2005-01-002			BRACKET - FWD	11 X 24 X .060 SHEET	1.6	AL SHEET										
		M C	1	2005-01-003	PREFLIGHT UMBILICAL	UMBILICAL PANEL ASSY	BRACKET - AFT	23 X 17 X .060 SHEET	3.7	AL SHEET										

ORIGINAL PAGE IS
OF POOR QUALITY

ORIGINAL PAGE IS
OF POOR QUALITY

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.	WEIGHT	MATERIAL / SPEC.	DRAWING OR REQUIREMENT SPEC. NUMBER	TEST REQMTS				
						M - MAKE	H - HORIZONTAL	X - TEST REQUIRED				DEVELOPMENT	QUALIFICATION	ACCEPTANCE	RECEIVING	SUB-SYSTEM
						B - BUY	V - VERTICAL	I - QUANTITY FOR TEST								
						O - OFF THE SHELF	C - COMMON									
						SECONDARY STRUCTURE NOMENCLATURE			DESCRIPTION							
						MODULE	ASSEMBLY	ITEM								
123.11.1	H	H	1	2106-00-000	X-1307 CROSS SUPPORT				317							
								CROSS TIE	3X3X.250X190 TUBE	139						
								ATTACH. PLATE	5X7X.50 PLATE	5						
								DIAGONAL	2X2X.250X110 TUBE	70						
								ATTACH ANGLE	5X5X.50X6 ANGLE	8						
								GUSSET	8X15X.375 PLATE	12						
12.11.1.6	H	C	1	2007-00-000	X-576 AIRMATS AIRMATS SUPP.				19.5							
								VERTICAL SUPPORT ASSY.		10.5						
								SUPPORT - FLOW FACE	15 1/2 X 57 X .040 SHEET	4						
								CENTER DIVIDER	1/2 X 1 1/2 X .032 X 59 CHANNEL	.5						
								EMI DIVIDER	1/2 X 1 1/2 X .025 X 59 ANGLE	.3						
								BRACKET - VERTICAL	1/2 X 1 1/2 X 2 X .050 X 1 NAT	.1						
								BRACKET - HORIZ.	1/2 X 1 1/2 X 2 X .050 X 1 NAT	.1						
								VERTICAL SUPPORT ASSY.	COVER	4						
								TRANSITION AIRMATS SUPP. ASSY.	DESIGN IS TBD ~ 25"	9						
								SUPPORT	15 1/2 X 28 X .040 SHEET	1.0						
								CENTER DIVIDER	1/2 X 1 1/2 X .032 X 28 CHANNEL	2.7						
								EMI DIVIDER	1/2 X 2 1/2 X .025 X 28 ANGLE	.5						
								BRACKET		.2						
								BRACKET		.5						
								COVER	19 X 28 X .032 SHEET	2						

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.	WEIGHT	MATERIAL/SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQMTS.					
						M: MAKE	H: HORIZONTAL	X: TEST REQUIRED				DEVELOPMENT	QUALIFICATION	ACCEPTANCE	RECEIVING	SUB-SYSTEM	SPARES
						B: BUY	V: VERTICAL	I: QUANTITY FOR TEST									
						O: OFF THE SHELF	C: COMMON										
SECONDARY STRUCTURE						NOMENCLATURE			DESCRIPTION								
MODULE	ASSEMBLY	ITEM															
12122a1	M	H	1	2108-00-000	MISSION SPECIALIST SECONDARY STRUCTURE				CONCEPTUAL DESIGN ONLY	67							
	M	H	1	2108-01-000	UPPER SUPPORT STRUCTURE					5.5							
	M	H	1	2108-01-001	CHANNEL SUPPORT				1 X 1 X 3 X .080 X 60 CHANNEL	3.6	AL SHEET						
	M	H	1	2108-01-002	BRACKET SUPPORT				4 X 4 X .070 X 3 ANGLE	.3	AL EXTRUSION						
	M	H	3	2108-01-003	ATTACH FITTING				1 1/2 X 3 X .090 X 1 1/2 TEE	.1	AL EXTRUSION						
	M	H		2108-01-004	UPPER SUPPORT STRUCTURE				MISC.	1.5							
	M	H	1	2108-02-000	CENTER SUPPORT STRUCTURE					18							
	M	H	1	2108-02-001	CHANNEL SUPPORT				1 X 1 X 3 X .080 X 60 CHANNEL	3.6	AL SHEET						
	M	H	6	2108-02-002	SECONDARY STRUCTURE				6 X 1 1/4 X 4 X .090 BEAM	1.8	AL BAR						
	M	H	1	2108-02-003	BRACKET SUPPORT				3 X 4 X .070 X 3 ANGLE	.1	AL EXTRUSION						
	M	H	2	2108-02-004	CENTER SUPPORT STRUCT.				MISC.	1.6							
	M	H	3	2108-03-000	UPPER CABINET ASSY				14 X 22 X 19 RIVETED ASSY.	83							
	M	H	2	2108-03-001	END PANEL				14 X 22 X .050 SHEET	1.5	AL SHEET						
	M	H	1	2108-03-002	FRONT PANEL				14 X 19 X .050 SHEET	1.8	AL SHEET						
	M	H	1	2108-03-003	TOP PANEL				15 X 19 X .050 SHEET	1.5	AL SHEET						
	M	H	4	2108-03-004	ATTACH ANGLE				1 X 1 X .060 X 19 ANGLE	.2	AL EXTRUSION						
	M	H	2	2108-03-005	ATTACH ANGLE				1 X 1 X .060 X 14 ANGLE	.2							
	M	H	2	2108-03-006	ATTACH ANGLE				1 X 1 X .060 X 19 ANGLE	.2							
	M	H	4	2108-03-007	UPPER CABINET ASSY.				ATTACH FITTING	.1	AL EXTRUSION						
	M	H	3	2108-04-000	LOWER CABINET ASSY				12 X 14 X 19 RIVETED ASSY	6.3							
	M	H	1	2108-04-001	FRONT PANEL				14 X 19 X .050 SHEET	1.3	AL SHEET						
	M	H	2	2108-04-002	END PANEL				12 X 14 X .050 SHEET	.8	AL SHEET						

ORIGINAL PAGE IS
OF POOR QUALITY

ORIGINAL PAGE 15
OF POOR QUALITY

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE		CONFIGURATION		TEST REQMTS.		WEIGHT	MATERIAL / SPEC.	DRAWING OR REQUIREMENT SPEC. NUMBER	TEST REQMTS.					
					M - MAKE	B - BUY	H - HORIZONTAL	V - VERTICAL	X - TEST REQUIRED	I - QUANTITY FOR TEST				DEVELOPMENT	QUALIFICATION	ACCEPTANCE	RECEIVING	SUB-SYSTEM	SYSTEM
					O - OFF THE SHELF		C - COMMON		DESCRIPTION										
					SECONDARY STRUCTURE NOMENCLATURE														
					MODULE	ASSEMBLY	ITEM												
		M H	1	2108-08-003					TOP PANEL	12 X 19 X .050	SHEET	1.2	AL SHEET						
		M H	4	2108-08-004					ATTACH ANGLE LMB	1 X 1 X .060 X 19	ANGLE	.2	AL EXTENSION						
		M H	2	2108-08-005					ATTACH ANGLE HMB	1 X 1 X .060 X 16	ANGLE	.2	AL EXTENSION						
		M H	2	2108-08-006					ATTACH ANGLE HMB	1 X 1 X .060 X 12	ANGLE	.1	AL EXTENSION						
		M H	4	2108-08-007			LOWER CABINET ASSY		ATTACH FITTING	1 1/2 X 3 X .090 X 1 1/2	TEE	.1	AL EXTENSION						
		M H	2	2108-00-001					FLOOR ATTACH FTG (LMBD)	2 X 3 X .090 X 1 1/2	TEE	.1	AL EXTENSION						
		M H	2	2108-00-002	MISSION SPECIALIST SECONDARY STRUCTURE					FLOOR ATTACH FTG (OUTD)	2 X 3 X .125 X 1 1/2	TEE	.1	AL EXTENSION					
12.122.03		M H	1	2109-00-000	PAYLOAD SPECIALIST SECONDARY STRUCTURE				SAME AS 2109-00-000	MISSION SPECIALIST CONSOLE		67							
12.122.02		M H	1	2110-00-000	ON-ORBIT STATION SECONDARY STRUCTURE					CONCEPTUAL DESIGN ONLY		424							
		M H	1	2110-01-000			CABINET ASSY.			18 X 56 X 60 RAISED ASSY.		40							
		M H	1	2110-01-001					FRONT PANEL	60 X 65 X .050	SHEET	197	AL SHEET						
		M H	2	2110-01-002					SIDE PANEL	18 X 56 X .050	SHEET	5	AL SHEET						
		M H	4	2110-01-003					FRONT SUPPORT ANGLE	1 X 1 X .050 X 65	ANGLE	.7	AL EXTENSION						
		M H	4	2110-01-004					HORIZONTAL SUPPORT-FRONT	1 X 1 X .050 X 60	ANGLE	.6							
		M H	4	2110-01-005					VERTICAL SUPPORT-REAR	1 X 1 X .050 X 56	ANGLE	.6							
		M H	4	2110-01-006			CABINET ASSY		HORIZONTAL SUPPORT-END	1 X 1 X .050 X 18	ANGLE	.2	AL EXTENSION						
		M H	6	2110-00-001	ON-ORBIT STATION SECONDARY STRUCTURE					FLOOR ATTACH	1 1/2 X 2 X .060 X 2	TEE	.4	AL EXTENSION					

A-10

SD76-SH-0092

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.	WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQMTS.								
						M = MAKE	H = HORIZONTAL	X = TEST REQUIRED				DEVELOPMENT	QUALIFICATION	RECEIVING	SUB-SYSTEM	SPARES				
						B = BUY	V = VERTICAL	I = QUANTITY FOR TEST												
						O = OFF THE SHELF	C = COMMON													
ELECTRONICS																				
NOMENCLATURE																				
MODULE						ASSEMBLY		ITEM	DESCRIPTION											
1.2.1.2.1					3001-00-000	OPERATORS CONSOLE				1800										
		C		1	3001-01-000		INPUT/OUTPUT CONTROL UNIT													
		B	C	1	3001-01-001			TAPE READER												
		B	C	1	3001-01-002			DISK DRIVE												
		B	C	1	3001-01-003			MAGNETIC TAPE UNIT												
		H	C	1	3001-01-004			CRT / KEYBOARD												
		H	C	1	3001-01-005			CONTROL PANEL - TEST SYSTEM												
		B	C	1	3001-01-006			CONTROLLER/DATA PROCESSOR UNIT (C/DPU)	28 K. PRIMARY											
		B	C	1	3001-01-007			C/DPU - I/O UNIT	CONSISTS OF TTY, CRT/ALCIB, LINE PRINTERS, I/O ELECTRONICS & AUXILIARY MEMORY.											
		B	C	1	3001-01-008			ELECTRONIC RACK												
		B	C	1	3001-01-009			CARD READER												
		B	C	1	3001-01-010			THERMAL CONTROL UNIT												
			C	1	3001-02-000		TEST MEASUREMENT UNIT													
		B	C	1	3001-02-001			TIME CODE GENERATOR												
		O	C	1	3001-02-002			INPUT PATCH PANEL												
		O	C	1	3001-02-003			THERMAL CONTROL UNIT												
		O	C	1	3001-02-004			WAVEFORM ANALYZER												
		O	C	1	3001-02-005			DIGITAL VOLTMETER												
		B	C	1	3001-02-006			FREQUENCY COUNTER												
		B	C	1	3001-02-007	OPERATORS CONSOLE	TEST MEASUREMENT UNIT	ELECTRONIC RACK												

IVE. HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.	WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQMTS.				
						M • MAKE	H • HORIZONTAL	X • TEST REQUIRED				DEVELOPMENT	QUALIFICATION	ACCEPTANCE	RECEIVING	SUB-SYSTEM
						B • BUY	V • VERTICAL	I • QUANTITY FOR TEST								
						O • OFF THE SHELF	C • COMMON									SPARES
ELECTRONICS NOMENCLATURE						DESCRIPTION										
MODULE		ASSEMBLY		ITEM												
OPERATOR'S CONSOLE (CONT)						AVIONICS I/F ELEMENT										
	12.1.2.4	M	C	1	3001-03-000								X			X
		O	C	1	3001-03-001			IVE LOGIC DC POWER SUPPLY						X		
		M	C	1	3001-03-002			C&W-DISP. & CONT. PNL.							X	
		M	C	1	3001-03-003			AUDIO UNIT								
		M	C	1	3001-03-004			CCTV UNIT								
		M	C	1	3001-03-005			CONTROL & DISP. PNL (P/L)								
		M	C	1	3001-03-006			AVIONICS I/F SM. UNIT							X	
		B	C	1	3001-03-007			ELECTRONIC BACK WIRING SET						X		
		B	C	1	3001-03-008			THEORETICAL CONTROL UNIT						X		
		B	C	1	3001-03-009	OPERATOR'S CONSOLE	AVIONICS I/F ELEMENT						X	X		
	12.1.2.3	C		1	3002-00-000	DC POWER SET			600				X			X
		B	C	1	3002-00-001			DC POWER SUPPLY					X			
		M	C	1	3002-00-002	DC POWER SET	REMOTE CONTROL PANEL	+ 28 VDC @ 400 AMPS (RESIDENT IN OPS CONSOLE)					X	X	X	
													X	X		
													X	X		
													X	X		
													X	X		

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.	WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQMTS							
						M - MAKE	H - HORIZONTAL	X - TEST REQUIRED				DEVELOPMENT	QUALIFICATION	RECEIVING	SUB-SYSTEM	SPARES			
						B - BUY	V - VERTICAL	I - QUANTITY FOR TEST				OPERATION	RECEIVING	RECEIVING	RECEIVING	RECEIVING			
						O - OFF THE SHELF	C - COMMON					RECEIVING	RECEIVING	RECEIVING	RECEIVING	RECEIVING			
ELECTRONICS NOMENCLATURE						DESCRIPTION													
MODULE						ASSEMBLY			ITEM										
12.12.2	H C	1	3004-00-000	AFT FLIGHT DECK SET									X	X	X				
	H C	1	3004-01-000				PAYLOAD STATION						X	X	X				
	H C	1	3004-01-001					ENCLOSURE					X	X	X				
	H C	1	3004-01-002					THERMAL CONTROL ASSEMBLY					X	X	X				
	H C	1	3004-01-003					AUDIO ASSEMBLY					X	X	X				
	H C	1	3004-01-004				PAYLOAD STATION	PATCH PANEL WIRING					X	X	X				
	H C	1	3004-02-000				ON-ORBIT STATION						X	X	X				
	H C	1	3004-02-001					FLOODLIGHT CONTROL PANEL					X	X	X				
	H C	1	3004-02-002					CCTV CONTROL PANEL					X	X	X				
	H C	1	3004-02-003					CCTV MONITOR					X	X	X				
	H C	1	3004-02-004					MISSION TIMER					X	X	X				
	H C	1	3004-02-005					PATCH PANEL					X	X	X				
	H C	1	3004-02-006				ON-ORBIT STATION	WIRING					X	X	X				
	H C	1	3004-03-000				MISSION STATION						X	X	X				
	H C	1	3004-03-001					C & W AND SAFETY PANEL					X	X	X				
	H C	1	3004-03-002					P/L POWER CONTROL PANEL					X	X	X				
	H C	1	3004-03-003					CRT/KC BOARD & DEU ASSEMBLY					X	X	X				
	H C	1	3004-03-004					COMMUNICATION CONTROL PANEL					X	X	X				
	H C	1	3004-03-005					ORDER C & W PANEL					X	X	X				
	H C	1	3004-03-006					AUDIO					X	X	X				
	H C	1	3004-03-007					FLOODLIGHT CONTROL PANEL					X	X	X				
	H C	1	3004-03-008					PATCH PANEL					X	X	X				
	H C	1	3004-03-009				MISSION STATION	WIRING					X	X	X				
	H C	2	3004-04-000	AFT FLIGHT DECK SET			AC INVERTER												
12.12.2	C	1	3007-00-000	EXTERNAL COMMUNICATION SYSTEM															
RELATED	B C	1	3007-00-001					MICROPHONE											
	B C	1	3007-00-002					LOUD SPEAKER											
	B C	1	3007-00-003					AMPLIFIER											
	H C	1	3007-00-004	EXTERNAL COMM. SYSTEM				CABLE SET											
ORIGINAL PAGE IS OF POOR QUALITY																			

DELETED

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE			CONFIGURATION			TEST REQMTS.			WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQMTS.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
						M • MAKE	B • BUY	O • OFF THE SHELF	H • HORIZONTAL	V • VERTICAL	C • COMMON	X • TEST REQUIRED	I • QUANTITY FOR TEST	DEVELOPMENT				QUALIFICATION	ACCEPTANCE	RECEIVING	SUB-SYSTEM	SPARES																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
						ELECTRONICS NOMENCLATURE						DESCRIPTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
						MODULE	ASSEMBLY	ITEM																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
12.1.2.4		M	H	1	3108-00-000	CABLE SET																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				

SD76-SH-0092

ITEM NUMBER	WBS NUMBER	SOURCE	CONF. IDENTIFICATION	QUANTITY	ILLUSTRATION NUMBER	SOURCE		CONFIGURATION		TEST REQMTS		WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT NUMBER	TEST REQUIREMENTS					
						M - MAKE	B - BUY	H - HORIZONTAL	V - VERTICAL	X - TEST REQUIRED	I - QUANTITY FOR TEST				DEVELOPMENT	QUALIFICATION	ACCEPTANCE	REWORKING	SUB-SYSTEM	SPARES
						OPTIONAL EQUIPMENT NOMENCLATURE		DESCRIPTION												
						MODULE	ASSEMBLY	ITEM												
12311.9		H	H	1	4101-00-000	X0576 RARLOCK INTERFACE						108								
		H	H	1	4101-00-001			RING-RARLOCK/TUNNEL INTERFACE	30" DIA X 2 X .625			88								
		H	H	2	4101-00-002			ATTACH BRACKET	2 X 6 K. 200 X 18 CHANNEL			9	CARBON STEEL ASTM-A-36	C6 X 8.2 CHANNEL						
		H	H	2	4101-00-003			ATTACH BRACKET	2 X 6 K. 200 X 18 CHANNEL			9	CARBON STEEL ASTM-A-36	C6 X 8.2 CHANNEL						
		B	H	8	4101-00-004			BOLT	1/2 DIA X 13 TPI X 1 1/2 LONG			2								
		B	H	12	4101-00-005	X0576 RARLOCK INTERFACE		BOLT	1/2 DIA X 1 1/2 LONG-FLAT HEAD			2								
12311.1		M	H	1	4102-00-000	X0660 TUNNEL INTERFACE						183								
		M	H	1	4102-01-001			RING-TUNNEL INTERFACE	47" DIA X 3.5 X .625 PLATE			30	AL. PLATE							
		H	H	1	4102-01-002			SUPPORT - LEFT	1 1/2 X 4 X .267 X 98 CHANNEL			51	CARBON STEEL ASTM-A-36	C6 X 8.25 CHANNEL						
		M	H	1	4102-01-003			SUPPORT - RIGHT	1 1/2 X 4 X .267 X 98 CHANNEL			51								
		H	H	1	4102-01-004			SUPPORT - FWD	1 1/2 X 4 K. 267 X 28 CHANNEL			15								
		H	H	1	4102-01-005	X0660 TUNNEL INTERFACE		SUPPORT - AFT	1 1/2 X 4 K. 267 X 69 CHANNEL			36	CARBON STEEL ASTM-A-36							
12311.9 12311.10		B/H	C	1	4003-00-000	PRIMARY LONGERON FITTING. NON-DEPLOYABLE PAYLOAD.	JOURNAL ASSEMBLY													
		B/H	C	1	4003-01-000			UPPER JOURNAL	5X5X13 FORGING				STEEL							
		B/H	C	1	4003-01-001			LOWER JOURNAL	5X6X13 FORGING				STEEL							
		B	C	1	4003-01-003			BEARING - BALL *	2.000 X 4.200 SPHERICAL BEARING				INCONEL 718 AMS 5663							
		H	C	2	4003-01-004			SHEAR PIN	.075 DIA X 1 LONG				STEEL							
		B	C	1	4003-01-005			BEARING - RACE *	1.750 X 5.375 DIAMETER				A-286 STEEL AMS 5757							
		H	C	1	4003-01-006			JOURNAL LOCK PIN	2.0 DIA X 5.125 LONG				STEEL							
		H	C	1	4003-01-007			JOURNAL LOCK BOLT	1.0 DIA X 3.0 LONG				STEEL							
		B	C	1	4003-01-008	PRIMARY LONGERON FITTING.	JOURNAL ASSEMBLY	BOLT	1.0 DIA X 4.50 LONG				STEEL							

ORIGINAL PAGE 13
OF POOR QUALITY

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.		WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQMTS.					
						M - MAKE	H - HORIZONTAL	X - TEST REQUIRED	I - QUANTITY FOR TEST				DEVELOPMENT	APPLICATION	RESEARCH	SUB-SYSTEM	SYSTEM	
						B - BUY	V - VERTICAL											
						O - OFF THE SHELF	C - COMMON											
OPTIONAL EQUIPMENT						NOMENCLATURE			DESCRIPTION									
MODULE	ASSEMBLY	ITEM																
123.11C 123.11.2	M	C	1	4104-00-000	- AUXILIARY KEEL FITTING				7 X 8 1/2 X 2	21	STEEL							
123.11.1.1	M	H	1	4105-00-000	P/L UPPER CLEARANCE GATE					73								
	M	H	2	4105-01-000	LEG SUPPORT ASSY.					25								
	M	H	2	4105-01-001				STIFFENER	1 1/2 X 2 X .060 X 92 ANGLE	2	AL. EXTRUSION							
	M	H	2	4105-01-002				STIFFENER	1 1/2 X 2 X .060 X 50 ANGLE	12	AL. EXTRUSION							
	M	H	1	4105-01-003				PANEL	38 X 97 X .060 SHEET	11	AL. SHEET							
	M	H	1	4105-01-004				GUSSET	4 X 20 X 1/2 X .060 CHANNEL	6	AL. SHEET							
	M	H	8	4105-01-005				STIFFENER	1 1/2 X 2 X .060 X 7 ANGLE	2	AL. EXTRUSION							
	M	H	1	4105-01-006				ROLLER SUPPORT, L.S.	4 X 10 X .250 SHEET	1	AL. SHEET							
	M	H	1	4105-01-007				ROLLER SUPPORT, RS	4 X 10 X .250 SHEET	1	AL. SHEET							
	M	H	2	4105-01-008				ROLLER	2.5 DIA X 1.5 LONG	7	AL. ROD							
	M	H	2	4105-01-009				SPLICE	1.5 DIA X 1 LONG	2	AL. ROD							
	B	H	2	4105-01-010	LEG SUPPORT ASSY.			BOLT	.50 DIA X 3 LONG	8	AL. ALLOY							
	M	H	1	4105-02-000	HORIZONTAL SUPPORT ASSY					13.6								
	M	H	1	4105-02-001				PANEL	15 X 92 X .060 SHEET	8	AL. SHEET							
	M	H	2	4105-02-002				STIFFENER	1 1/2 X 2 X .060 X 92 ANGLE	2	AL. EXTRUSION							
	M	H	4	4105-02-003	HORIZONTAL SUPPORT ASSY.			STIFFENER	1 1/2 X 2 X .060 X 15 ANGLE	0.8	AL. EXTRUSION							

UTILIZATION LIST:

ITEM	QUANTITY	UNIT	CONFIGURATION	TEST REQUIREMENTS	WEIGHT	MATERIAL SPEC.	DETAILED DRAWING NO.	TEST REQUIREMENTS												
								TENSILE	COMPRESSION	BENDING	SHEAR	WELD	FINISH	PAINT	SPRINKLER					
123.11.1			UPPER CLEARANCE GAGE (CONT'D)																	
M H 4	#105-00-001			PANEL ATTACH ANGLE	9X15 X .375 SHEET -84%	3.5	AL SHEET													
D H 10	#105-00-002			BOLT	.375 X 1 1/2 LONG	.2	AL ALLOY													
M H 2	#105-03-000		SIDE GAGE ASSY			2.2														
M H 1	#105-03-001			GAGE SEGMENT	12 X .060 X 87 SHEET 50%	.6	AL SHEET													
M H 3	#105-03-002		SIDE GAGE ASSY	ATTACH CLIP	2X2 X .060 X 2 ANGLE	.05	AL EXTRUSION													
M H 1	#105-08-000		CENTER GAGE ASSY			6.8														
M H 1	#105-08-001			GAGE SEGMENT	12 X .060 X 90 SHEET 50%	6.5	AL SHEET													
M H 5	#105-03-002		CENTER GAGE ASSY	ATTACH CLIP	3 ANGLES #105-03-002 CLIP	.05	AL EXTRUSION													
M H 2	#105-00-003		UPPER CLEARANCE GAGE	GUIDE RAIL	1 1/2 X 3 X 3 X .100 X 240 SEE DESIGN TWO.	37	AL EXTRUSION													
M H 1	#106-00-000		LOWER CLEARANCE GAGE			152														
M H 1	#106-01-000		CENTER GAGE ASSY			426														
M H 1	#106-01-001			CENTER TEMPLATE	16 X 88 X .100 SHEET -60%	11.6	AL SHEET													
M H 1	#106-01-002			TEMPLATE SUPPORT	39 X 73 X .100 SHEET -50%	29.5	AL SHEET													
M H 2	#106-01-003			DIAGONAL SUPPORT	11 X 21 X .125 SHEET -60%	2.0	AL SHEET													
M H 2	#106-01-004			TRANSVERSE ANGLE	1 1/2 X 1 1/2 X .125 X 57 ANGLE	.10	AL EXTRUSION													
M H 2	#106-01-005			BASE SUPPORT	1 3/8 X 2 X .125 X 20 CHANNEL	.15	AL EXTRUSION													
M H 4	#106-01-006			ROLLER	2 3/4 DIA X 1 ROD	.6	AL ALLOY ROD													
B H 4	#106-01-007			AXLE	.250 DIA X 1 1/8 LONG BOLT	.1	AL ALLOY													
B H 4	#106-01-008			NUT	.250 DIA NUT	-	AL ALLOY													
B H 9	#106-01-009		CENTER GAGE ASSY	WASHER / SHIM		-	AL ALLOY													
M H 1	#106-00-001			CENTER ROLLER GUIDE	7/8 X 3 1/4 X .281 X 240 CHANNEL	34.	AL EXTRUSION													
M H 1	#106-00-002			OUTER ROLLER GUIDE	7/8 X 1 1/2 X .125 X 240 CHANNEL	10.6	AL EXTRUSION													

ORIGINAL PAGE IS
OF POOR QUALITY

ORIGINAL PAGE IS
OF POOR QUALITY

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.	WEIGHT	MATERIAL / SPEC.	DRAWING OR REQUIREMENT SPEC. NUMBER	TEST REQMTS.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
						M = MAKE	H = HORIZONTAL	X = TEST REQUIRED				DEVELOPMENT	QUALIFICATION	ACCEPTANCE	RECEIVING	SUB-SYSTEM	SPARES																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
						B = BUY	V = VERTICAL	I = QUANTITY FOR TEST																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
						O = OFF THE SHELF	C = COMMON																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
OPTIONAL EQUIPMENT NOMENCLATURE									DESCRIPTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
MODULE			ASSEMBLY			ITEM																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
123.11.1					4106-00-000	LOWER CLEARANCE BASE (CONT'D)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.	WEIGHT	MATERIAL/SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQUIREMENTS					
						M • MAKE	H • HORIZONTAL	X • TEST REQUIRED				DEVELOPMENT	QUALIFICATION	ACCEPTANCE	RECEIVING	SUB-SYSTEM	
						B • BUY	V • VERTICAL	I • QUANTITY FOR TEST									
						O • OFF THE SHELF	C • COMMON										
						OPTIONAL EQUIPMENT NOMENCLATURE			DESCRIPTION	LBS.							
MODULE	ASSEMBLY	ITEM															
12.3.1.1.K		H	C	1	4107-00-000	0MS Δ V ENVELOPE			DESIGN IS TBD. USE THREE-JOY ADD ON APPROACH.								
		H	C	1	4107-01-000		500 FPS Δ VELOCITY										
		H	C	1	4107-02-000		1000 FPS Δ VELOCITY		ADD ON TO BASIS 500 FPS								
		H	C	1	4107-03-000	0MS Δ V ENVELOPE	1500 FPS Δ VELOCITY		ADD ON TO 1000 FPS.								
12.3.3.1a		H	H	1	4108-00-000	FLOODLIGHT X0.5% BULKHEAD.				2.4							
		B	H	1	4108-00-001			DOCKING FLOODLIGHT	LIGHT SELECTOR IS TBD.	2							
		H	H	2	4108-00-002			BRACKET	4 X 8 X .060 SHEET	2	AL. ALLOY						
		H	H	1	4108-00-003			WIRE HARNESS									
		B	C	1	4108-00-004	FLOODLIGHT-X0.5% BULKHEAD.		SWITCH									
12.12.2.05 12.3.3.1f		H	C	4	4009-00-000	X0.5% PAYLOAD SERVICE PANEL				2.0							
		H	C	1	4009-01-000		SERVICE PANEL ASSY			2.0							
		H	C	1	4009-02-001			PANEL	8 X 16 X .180 SHEET	1.0	AL. SHEET						
		B	C	9	4009-03-002	X0.5% PAYLOAD PANEL	SERVICE PANEL ASSY	CONNECTOR-FEED THRU	WELDN FEED-THRU CONNECTOR DUSTSCH ELECTRIC CO.	.1							
12.3.2.1a		H	I	1	4110-00-000	ENVIRONMENTAL CONTROL UNIT SET.			DESIGN IS TBD								
		B	H	1	4110-01-000		HEAT EXCHANGER										
		H	H	1	4110-02-000		CONTROL & DISPLAY										
		B	H	1	4110-03-000		PURGE & TEST										
		B	H	1	4110-04-000		FLUID LINES SET										
		H	H	1	4110-05-000	ENVIRONMENTAL CONTROL UNIT SET.	INTERFACE PANEL ASSY.										

ORIGINAL PAGE 11
OF POB. QUANTITY

4013827
CONTROL SPEC
ORIGINAL PAGE 13
OF FOUR QUALITY

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE		CONFIGURATION		TEST REQMTS.		WEIGHT	MATERIAL / SPEC.	DRAWING OR DOCUMENT SPEC. NUMBER	TEST REQMTS.					
					M	O	H	V	X	I				DEVELOPMENT	QUALIFICATION	ACCEPTANCE	REWORKING	SUB-SYSTEM	
					M	B	H	V	X	I									
					O														
OPTIONAL EQUIPMENT NOMENCLATURE						MODULE		ASSEMBLY		ITEM		DESCRIPTION							
1.5.1	DELETED	B	H	3	4111-00-000	CASTERS						655		DELETED					
				4	4111-01-000			CASTER ASSY - SWIVEL				50	L.A. CALIF.						
				2	4111-00-001					DIAGONAL SUPPORT		19	CARBON STEEL ASTM-A36						
				2	4111-00-002					PLATE - SUPPORT		29	CARBON STEEL ASTM-A36(1)						
				4	4111-00-003					ANGLE - ATTACH		35	CARBON STEEL ASTM-A36						
				4	4111-00-004					DIAGONAL			"						
				12	4111-00-005	CASTERS				BOLT		.2	.50 DIA X 2						
				1	4012-00-000	HOISTING						781							
				2	4012-00-001					BEAM - SPREADER		372	CARBON STEEL ASTM-A36						
				4	4012-00-002					ATTACH LUG		3.4	CARBON STEEL ASTM-A36(1)						
				4	4012-00-003					CLEVIS		.5	STEEL ALLOY						
				6	4012-00-004	HOISTING				BOLT		.2	.50 DIA X 2						
				1	4013-00-000	TOWING		(USE R.I. STANDARD)		11EN-B-0244 TOW BAR		280							
				2	4013-01-000			ATTACH ASSY (L&R)				185							
				1	4013-01-001					ATTACH ANGLE		5	CARBON STEEL ASTM-A36						
				1	4013-01-002					LUG		3.4	CARBON STEEL ASTM-A36(1)						
1.5.1	DELETED	B	H	4	4013-01-003			ATTACH ASSY.		BOLT		.2	STEEL ALLOY	DELETED					
				1	4013-02-000			TONGUE ASSY				254							
				2	4013-02-001					TOW BAR (L&R)		86	CARBON STEEL ASTM-A36						
				1	4013-02-002					CROSS BAR		74	CARBON STEEL ASTM-A36						
				2	4013-02-003					CLEVIS		.5	STEEL ALLOY						
				1	4013-02-004	TOWING		TONGUE ASSY		RING		12	STEEL						

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.	WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQMTS.								
						M • MAKE	H • HORIZONTAL	X • TEST REQUIRED				DEVELOPMENT	QUALIFICATION	APPROPRIATE	RECEIVING	SUB-SYSTEM				
						B • BUY	V • VERTICAL	I • QUANTITY FOR TEST				SYSTEM	SPARES							
						O • OFF THE SHELF	C • COMMON													
						OPTIONAL EQUIPMENT NOMENCLATURE			DESCRIPTION											
						MODULE	ASSEMBLY	ITEM												
	12331C	C		1	4018-00-000	TV, X-576 BULLHEAD														
		C		1	4018-01-000		TV CAMERA ASSY													
		B	C	1	4018-01-001			CAMERA, B & W	COND MODEL 440											
		B	C	1	4018-01-002			LENS	CANNON 15-105MM BODY											
		B	C	1	4018-01-003			HEAD-TILT & PAN	PERCO # 550											
		B	C	1	4018-01-004		TV CAMERA ASSY.	VIDEOCAM TUBE	ZCA # 8521											
		H	C	1	4018-02-000		REMOTE CONTROL UNIT													
		B	C	1	4018-02-001			ZOOM CONTROL	PERCO											
		B	C	1	4018-02-002			TILT & PAN CONTROL	PERCO											
		H	C	1	4018-02-003		REMOTE CONTROL UNIT	CONTROL PANEL				AL SHEET								
		H	C	1	4018-03-000		CAMERA INSTL.													
		H	C	1	4018-03-001			BASE	15 X 10 X .050			AL SHEET								
		H	C	2	4018-03-002			BRACKET	15 X 6 X .050			AL SHEET								
		H	C	1	4018-03-003		CAMERA INSTL.	CABLE SET	POWER, CONTROL & MONITOR											
		B	C	1	4018-04-000		TV MONITOR ASSY													
		B	C	1	4018-04-001			MONITOR UNIT	SONY # 980 - 9" SCREEN											
		H	C	1	4018-04-002			BASE	12 X 12 X .050			AL SHEET								
		H	C	2	4018-05-003	TV, X-576	TV MONITOR ASSY	BRACKET	4 X 12 X .050			AL SHEET								

ORIGINAL PAGE IS
OF POOR QUALITY

ORIGINAL PAGE IS
OF POOR QUALITY

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.	WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQMTS.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
						M - MAKE	H - HORIZONTAL	X - TEST REQUIRED				DEVELOPMENT	QUALIFICATION	ACCEPTANCE	RECEIVING	SUB-SYSTEM	SPARES																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
						B - BUY	V - VERTICAL	I - QUANTITY FOR TEST																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
						O - OFF THE SHELF	C - COMMON																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
OPTIONAL EQUIPMENT NOMENCLATURE									DESCRIPTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
MODULE	ASSEMBLY	ITEM																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
1233.1C		H	1	4115-00-000	TV, X ₀ 1307 BULKHEAD																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.	WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQUIREMENTS						
					M - MAKE B - BUY O - OFF THE SHELF	H - HORIZONTAL V - VERTICAL C - COMMON	K - TEST REQUIRED P - QUANTITY FOR TEST				DEVELOPMENT	QUALIFICATION	ACCEPTANCE	RECEIVING			
					OPTIONAL EQUIPMENT NOMENCLATURE		DESCRIPTION								SUB-SYSTEM	SPARES	
					MODULE	ASSEMBLY											ITEM
1.2.3.1.1	M	H	3	4116-00-000	PAYLOAD BAY LINER			493	X 3 - 1477								
	M	H	14	4116-00-001			FRAME	90X240 X .050 X 100	NET	2.2	ALUM EXTRUSION	13043-3521-0005					
	M	H	4	4116-00-002			FRAME-END	75X.075X.063 X 100	SEE	1.5		AND 10138-0704					
	M	H	8	4116-00-003			SUPPORT-LONGERON	20X1.75 X .125 X .840	TEE	11.4		AND 10136-2000					
	M	H	8	4116-00-004			SUPPORT-LONGERON	1 X 2.00 X .050 X .60	ANGLE	.9	AL EXTRUSION						
	M	H	6	4116-00-005			BRACKET NO. 1 (L/R)	4 X 6 X .030	SHEET	.1	AL SHEET						
	M	H	6	4116-00-006			BRACKET NO. 2 (L/R)	6 X 17 X .060	SHEET	.5							
	M	H	6	4116-00-007			BRACKET NO. 3 (L/R)	6 X 14 X .060	SHEET	.4							
	M	H	6	4116-00-008			BRACKET, NO. 4 (L/R)	4 X 7 X .050	SHEET	.1	AL SHEET						
	M	H	4	4116-00-009			LINING NO. 1	48X120 REX $\frac{3}{8}$ " - NO. 13		32	L.C. STEEL EXPANDED METAL						
	M	H	8	4116-00-010			LINING NO. 2	36 X 120 REX $\frac{3}{8}$ " - NO. 13		24							
	M	H	2	4116-00-011			LINING NO. 3	24 X 120 REX $\frac{3}{8}$ " - NO. 13		16	L.C. STEEL EXPANDED METAL						
1.2.3.3.1	M	C	1	4017-00-000	PREFLIGHT UNIBLOCK ELECTRICAL PANEL			5									
	M	C	1	4017-00-001			UNIBLOCK PANEL	13 X 18 X .250	SHEET	.5	AL SHEET						
	M	C	TBD	4017-00-002			ELECTRICAL CONNECTOR	LOCATION & NUMBER ARE TBD.									
1.2.3.2.1	M	C	1	4018-00-000	PREFLIGHT UNIBLOCK FLUID PANEL			5									
	M	C	1	4018-00-001			UNIBLOCK PANEL	11 X 18 X .250	SHEET	.5	AL SHEET						
	M	C	TBD	4018-00-002			FLUID COUPLERS	LOCATION & NUMBER ARE TBD.									
1.2.3.3.1	M	C	1	4019-00-000	PAYLOAD BAY FLOODLIGHT			43									
	M	C	6	4019-00-001			FLOODLIGHT	6 X 12 X 9" BOX (LANT TBD)		.6							
	M	C	2	4019-00-002			BRACKET 1 UPPER	10 X 10 X .060	SHEET	.4	AL SHEET						
	M	C	2	4019-00-003			BRACKET 1 LOWER	10 X 10 X .060	SHEET	.6	AL SHEET						
	M	C	4	4019-00-004			BRACKET 2 UPPER	20 X 22 X .060	SHEET	2.6	AL SHEET						
	M	C	4	4019-00-005			BRACKET 2 LOWER	15 X 18 X .060	SHEET	1.6	AL SHEET						
	M	C	6	4019-00-006			WIRE HARNESS SWITCH			TBD.							

ORIGINAL PAGE IS
OF 2008

ORIGINAL PAGE IS
OF POOR QUALITY

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.	WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT NUMBER	TEST REQMTS.				
						M = MAKE	H = HORIZONTAL	% = TEST REQUIRED				DEVELOPMENT	QUALIFICATION	ACCEPTANCE	REVIEWING	SUB-SYSTEM
						B = BUY	V = VERTICAL	1 = QUANTITY FOR TEST				SYSTEM	SPARES			
						O = OFF THE SHELF	C = COMMON									
OPTIONAL EQUIPMENT								DESCRIPTION								
NOMENCLATURE																
MODULE		ASSEMBLY		ITEM.												
12.1.1.6	M	H	1	4120-00-000	Xo 1307 BULKHEAD				325							
	M	H	1	4120-01-000		BULKHEAD ASSY.	SHAFTS TO Xo 576 BULKHEAD ASSY IN DESIGN, MATERIAL AND FABRICATION. ALL ESTIMATES SHOULD BE BASED ON Xo 576 BULKHEAD EXHAUST MOTOR IF 3.									
	M	H	1	4120-02-000	Xo 1307 BULKHEAD	BULKHEAD ASSY.										
12.3.2.6	M	H	1	4121-00-000	Xo 1307 P/L OXIDIZER / FUEL PANELS				50							
	M	H	1	4121-01-000		OXIDIZER PANEL ASSY (LS)			14.6							
	M	H	1	4121-01-001			PANEL	12 X 12 X .250 SHEET	3.6	AL. SHEET						
	B	H	1	4121-01-002			FLUID COUPLING (M)	6" DIA	11	STAINLESS STEEL						
	M	H	1	4121-02-000		OXIDIZER PANEL PANEL (LS)			5.2							
	M	H	1	4121-02-001			PANEL	12 X 12 X .250 SHEET	3.6	AL. SHEET						
	B	H	1	4121-02-002			COUPLING	1" DIA.	1	STAINLESS						
	B	H	1	4121-02-003			COUPLING	1/2" DIA.	.6	STAINLESS						
	M	H	1	4121-03-000		FUEL PANEL ASSY (RS)			15.6							
	M	H	1	4121-03-001			PANEL	12 X 12 X .250 SHEET	3.6	AL. SHEET						
	B	H	1	4121-03-002			FLUID COUPLING (M)	3.5" DIA	7.	STAINLESS						
	B	H	1	4121-03-003			FLUID COUPLING (M)	2.5" DIA	5	STAINLESS						
	M	H	1	4121-04-000		FUEL PANEL ASSY (RS)			14.6							
	M	H	1	4121-04-001			PANEL	12 X 12 X .250 SHEET	3.6	AL. SHEET						
	B	H	1	4121-04-002			FLUID COUPLING (M)	4" DIA.	8	STAINLESS						
	B	H	1	4121-04-003			FLUID COUPLING (M)	1 1/2" DIA.	2							
	B	H	1	4121-04-004		Xo 1307 P/L OXIDIZER / FUEL PANELS			FLUID COUPLING (M)	1" DIA	1	STAINLESS				

IVE HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE	CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.		WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQMTS.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
						M • MAKE	H • HORIZONTAL	X • TEST REQUIRED					DEVELOPMENT	QUALIFICATION	PERFORMANCE	REPAIRING	SUB-SYSTEM																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
						B • BUY	V • VERTICAL	I • QUANTITY FOR TEST																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
						O • OFF THE SHELF	C • COMMON																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
TEST EQUIPMENT						NOMENCLATURE			DESCRIPTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
MODULE			ASSEMBLY		ITEM																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
15.1		H	H	1	4122-00-000	PAYLOAD MASS SIMULATOR				65,000																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			

IVE - HARDWARE UTILIZATION LIST

ITEM NUMBER	WBS NUMBER	SOURCE CONFIGURATION	QUANTITY	IDENTIFICATION NUMBER	SOURCE	CONFIGURATION	TEST REQMTS.		WEIGHT	MATERIAL / SPEC.	DRAWING OR PROCUREMENT SPEC. NUMBER	TEST REQMTS.				
					M - MAKE	H - HORIZONTAL	X - TEST REQUIRED	DEVELOPMENT				QUALIFICATION	ADAPTANCE	REWORKING	SUB-SYSTEM	
					B - BUY	V - VERTICAL	I - QUANTITY FOR TEST									
					O - OFF THE SHELF	C - COMMON										
OPTIONAL EQUIPMENT																
NOMENCLATURE										DESCRIPTION						
MODULE			ASSEMBLY			ITEM										
12.3.2.1.a	M	H	1	4124-00-000	Xo 1307 ELECTRICAL SERVICE PANEL				9.4							
	M	H	1	4128-01-000	PANEL ASSY. (LH.)				4.7							
	M	H	1	4128-01-001	PANEL (LH.)			12 X 12 X .250 SHEET	3.5	AL ALLOY						
	B	H	1	4128-00-001	CONNECTOR - POWER			36 SHIELD SIZE CONNECTOR	.6	AL ALLOY						
	B	H	2	4128-00-002	PANEL ASSY (LH)			CONNECTOR - SIGNAL	22 SHIELD SIZE CONNECTOR	.3	AL ALLOY					
	M	H	1	4128-02-000	PANEL ASSY (RH)				4.7							
	M	H	1	4128-02-001	PANEL (RH)			12 X 12 X .250 SHEET	3.5	AL ALLOY						
	B	H	1	4128-00-001	CONNECTOR - POWER			36 SHIELD SIZE	.6	AL ALLOY						
	B	H	2	4128-00-002	Xo 1307 SERVICE PANEL ASSY (RH)			CONNECTOR - SIGNAL	22 SHIELD SIZE	.3	AL ALLOY					
12.3.2.1.f	M	H	1	4125-00-000	KEEL FITTING, X AND Y LOADS			TX 8/16 X 2	2.1	STEEL	DELETED					
12.1.1.1.d 12.3.1.6	M	H	1	4126-00-000	STABILIZING LONGERON FITTING, NON-DEPLOYABLE PAYLOAD			IDENTICAL TO KIT 4003-00-000 EXCEPT SHIELD PAN (PN 4003-01-002) IS NOT REQUIRED.								
12.3.2.1.g	M	C	1	4127-00-000	CABLE SETS											
	M	C	1	4127-01-000	Xo 1307 POWER CABLE SET			TBD								
	M	C	1	4127-02-000	CABLE SETS			Xo 1307/T-O CABLE SET	TBD							
12.3.1.1.m	M	H	1	4128-00-000	T-O UNIBUSICAL PROVISIONS											
	M	H	1	4128-01-000	L.H. PANEL ASSEMBLY			TBD								
	M	H	1	4128-02-000	T-O UNIBUSICAL PROV. R.H. PANEL ASSEMBLY			TBD								
12.3.2.1.c	M	H	1	4129-00-000	T-O UNIBUSICAL FLUID I/F ASSY.			TBD								

ORIGINAL PAGE IS
OF POOR QUALITY

ORIGINAL PAGE IS
OF POOR QUALITY



APPENDIX B

HORIZONTAL IVE IN-FIELD ASSEMBLY PROCEDURE



B-1. INTRODUCTION

This Appendix contains an in-field assembly procedure for the Horizontal IVE and assumptions/guidelines employed. The in-field assembly procedure was developed to increase the degree of confidence in the basic IVE design approach by identifying possible problem areas associated with the IVE design. An iterative procedure was used resulting in a compatible design and in-field assembly procedure as discussed in Section B-3 of this appendix.

B-2. COMMENTS

The following comments apply to the procedures discussed in Section B-3 of this appendix.

1. The X, Y, Z coordinate system used in the IVE structure assembly procedure is the same as the Shuttle Orbiter coordinate system.
2. Special tools/aids required during the assembly of the IVE structure consists of two (2) spreader/hoist bars and two (2) master alignment tools which are contractor furnished.
3. No special tools are required to be provided by the User for the assembly of the structure. However, it is assumed that standard facility equipment such as an overhead hoist/crane, forklift, optical transit, targets, and levels will be available during assembly operations.
4. The assembly procedure is predicated upon the premise that the structure has been assembled, aligned, verified and disassembled by the Contractor prior to delivery to the User.
5. Upon completion of assembly and verification of alignment the nuts on all the bolted connections shall be "sealed" with a material similar to locktite to prevent inadvertent loosening of bolts.
6. It is anticipated that at the 100% drawing completion milestone an identification code will be devised and each part of the IVE structure marked. The coding will be incorporated in the in-field assembly procedure to facilitate assembly by the User.



B-3. IN-FIELD ASSEMBLY PROCEDURE

A. Section 2 Assembly. (See Figure B-1 View B)

- A.1. Position 4 floor plates on floor to form rectangle approximately 16 feet by 20 feet.
- A.2. Position 3 cross beams on support blocks between floor plates at 10 foot intervals.
- A.3. Using overhead hoist, position right hand truss assembly on floor plates. Position end of cross beam between Horizontal attach plates at three places along bottom of truss assembly.
- A.4. Bolt cross beams to truss assembly. (Do not torque bolts at this time).
- A.5. Position and bolt right hand knee braces to truss assembly and three cross beams. (Do not torque bolts at this time).
- A.6. Repeat Steps A.3, A.4 and A.5 for left hand truss assembly.
- A.7. Detach overhead hoists from right and left hand truss assemblies.
- A.8. Attach spreader bars to longeron at each end of Section assembly as shown in Figure B-1 View C.
- A.9. Position diagonal tie rods below cross beams and attach to left and right truss assemblies.
- A.10. Level bridge rails with floor screw jacks in the X and Y planes (Use facility optical equipment).
- A.11. Square section assembly by adjusting tie rods.
- A.12. Plumb truss assemblies in the vertical plane by adjusting knee braces.
- A.13. Remove spreader bars from section assembly.



- A.14. Position master alignment tool at each end of section assembly as shown in Figure B-1 View D and check alignment of shear pin holes in rails. If no fit, repeat steps A.10, A.11 and A.12 as required.
- A.15. Install tooling dowel pins as provided for at the bolted connections.
- A.16. Torque all bolts to specified values.
- A.17. Position and attach two keel beams at Y_0 centerline.
- A.18. Position and attach keel longerons to keel and cross beams. Check location using master alignment tool.
- A.19. Install tooling dowel pins in keel beams and longerons.
- A.20. Torque keel bolts to specified values.
- A.21. Remove master alignment tools from section assembly.
- A.22. Verify final alignment. (Assembly of Section 2 is complete).

Section 3 Assembly. (See Figure B-1 View E)

- B.1. Position 2 floor plates on floor 20 feet aft of and in line with Section 2 assembly.
- B.2. Position 3 cross beams on support blocks between floor plates at 10 foot intervals. (The 2 floor plates at Station $X_{01063.3}$ are shared by Sections 2 and 3).
- B.3. Using overhead hoist, position right hand truss assembly so upper longeron is in line with splice plate on Section 2 longeron and insert one bolt.



- B.3.a Adjust screw jacks to align both upper and lower splice plates between sections 2 and 3 and install remaining bolts. (Do not torque bolts at this time).
- B.4. Position end of cross beam between horizontal attach plates at three places along bottom of truss assembly and bolt cross beams to truss. (Do not torque bolts at this time).
- B.5. Position and bolt right hand knee braces to truss assembly and three cross beams. (Do not torque bolts at this time).
- B.6. Repeat steps B.3., B.3.a, B.4. and B.5 for left hand truss assembly.
- B.7. Detach overhead hoist from left and right truss assemblies.
- B.8. Attach spreader bar to longerons at aft end of Section 3 as shown in Figure B-1 View F.
- B.9. Repeat Steps A.9 through A.13 for Section 3.
- B.10. Position master alignment tool to span joint between Section 2 and 3 as shown in Figure B-View A. Position second alignment tool at aft end of Section 3.
- B.11. Check alignment of shear pin holes in rails at each tool. If no fit, repeat steps A.10, A.11 and A.12 as required.
- B.12. Install tooling dowel pins as provided for at the bolted connections.
- B.13. Torque all bolts to specified values.
- B.14. Position and attach two keel beams to the cross beams at Y₀ centerline (Figure B-2 View A).
- B.15. Attach Section 3 keel longerons to keel beams and check alignment of keel fitting attach holes with master alignment tool across Section joint at Station X₀ 1063.3.



- B.16. Install tooling dowel pins in keel beams and longerons.
- B.17. Torque keel bolts to specified values.
- B.18. Remove master alignment tools from Section assembly.
- B.19. Verify alignment of rails and keel longerons for Section 2 and 3.
- C. Section 1 Assembly. (See Figure B-2 View B)
 - C.1 Position 2 floor plates on floor 20 feet forward of and in line with Section 2 assembly.
 - C.2 Position 3 cross beams on support blocks between floor plates at 10 foot intervals. (The 2 floor plates at Station X₀819.66 are shared by Sections 1 and 2).
 - C.3 Using overhead hoist, position right hand truss assembly so upper longeron is in line with splice plate at forward end of Section 2 and insert one bolt.
 - C.4 Adjust screw jacks to align both upper and lower splice plates between Sections 1 and 2 and install remaining bolts. (Do not torque bolts at this time)
 - C.5 Position end of cross beam between horizontal attach plates at three places along bottom of truss assembly and bolt cross beams to truss. (Do not torque bolts at this time).
 - C.6. Position and bolt right hand knee braces to truss assembly and three cross beams. (Do not torque bolts at this time).
 - C.7. Repeat Steps C.3, C.4, C.5 and C.6 for left hand truss assembly.
 - C.8. Detach overhead hoist from left and right truss assemblies.



- C.9. Attach spreader bar to longeron at forward end of Section 1.
- C.10. Repeat Steps A.9 through A.13 for Section 1.
 - C.10.a Remove spreader bar from Section assembly.
- C.11 Position master alignment tool to span joint between Section 1 and 2 as shown in Figure B-2 View C. Position second alignment tool at forward end of Section 1.
- C.12. Check alignment of shear pin holes in rails at each tool. If no fit, repeat Steps A.10, A.11 and A.12 as required.
- C.13. Install tooling dowel pins as provided for at the bolted connections.
- C.14. Torque all bolts to specified values.
- C.15. Position and attach two keel beams to cross beams at Y_0 centerline.
- C.16. Attach Section 1 keel longerons to keel beams and check alignment of keel fitting attach holes with master alignment tool across Section joint at Station $X_{0819.66}$.
- C.17. Install tooling dowel pins in keel beams and longerons.
- C.18. Torque all bolts to specified values.
- C.19. Remove master alignment tools from Section 1 assembly.
- C.20. Verify alignment of rails and keel longerons Sections 1, 2 and 3 using transit and targets fixed to pin holes. The assembly of Sections 2 and 3 is complete.

MS/PS/OOS Support Structure. (See Figure B-2 View D)

- D.1 Position left hand welded support assembly at Station $X_0=576$ and $Y_0=100$ to index with upper and lower gusset attach plates on forward end of Section 1.
- D.2 Position 3 floor plates under screw jacks at corner corners of support assembly. (The floor plate at the forward corner of Section 1 is shared with the support assembly).
- D.3 Level and align L.H. support assembly with screw structure jacks.
- D.4 Bolt gusset plates and vertical member of support assembly together at $X_0=576$.
- D.5 Install tooling dowel pins in gusset plates.
- D.6 Repeat Steps D.1 through D.5 for right hand support assembly.
- D.6.a Install floor beams connecting LH & RH support assemblies.
- D.7 Install center floor panel between support assemblies at $Z_0=419$.
- D.8 Install lower support assembly braces connecting LH and RH support assemblies.
- D.9 Bolt handrails to floor panels on the left and right support assemblies.

 $X_0=576$ Bulkhead Assembly. (See Figure B-2 View D)

- E.1 Using overhead hoist, position bulkhead assembly on top of MS/PS support assembly with aft face of bulkhead at station $X_0=576$.
- E.2 Bolt lower attach angle of bulkhead to horizontal member of support assembly. (Do not torque bolts at this time).



- E.3 Position and bolt 2 diagonal braces to bulkhead and floor structure. (Do not torque bolts at this time).
 - E.4 Center bulkhead on $Y_0=0$ scribe line and align aft surface of bulkhead in the vertical plane by adjusting diagonal braces.
 - E.5 Install tooling dowel pins as provided for in bolted connections.
 - E.5a Torque bolts to specified values.
 - E.6 Attach handrails to outboard edge of bulkhead structure.
- F. X_0 576 Bulkhead Assembly. (See Figure B-2 View E)
- F.1 Assemble 3 panels of bulkhead together in a horizontal position.
 - F.2 Using overhead hoist, position bulkhead assemble at Station X_0 1307 to mate with support angle (L and R side) attached to aft end of Section 3 assembly and bolt together. (Do not torque bolts at this time).
 - F.3 Center bulkhead on $Y_0=0$ scribe line and align forward surface of bulkhead in a vertical plane at Station X_0 1307.
 - F.4 Bolt lower half of bulkhead to attach structure on aft end on Section 3 assembly. (Do not torque bolts at this time).
 - F.5 Install tooling dowel pins as provided for at the bolted connections.
 - F.6 Torque all bolts to specified values.
- G. Payload Wire Tray Assembly
- G.1 Install wire tray attach clips to the knee braces on left and right sides of Section 1, 2 and 3 assemblies. Index to scribe lines on knee brace.



- G.2 Position master alignment tool at each end of
----- Section 1 assembly engaging rails and keel fitting.
Attach wire tray index template to alignment tool.
- G.3 Position 20 foot sections of wire tray assemblies
----- between attach clips on knee braces on left and
----- right side of Sections 1, 2 and 3.
- G.4 Index wire tray assemblies to template at each
----- end of Section 1 and bolt in place. Also bolt
tray to center knee brace.
- G.5 Repeat Steps G.2, G.3 and G.4 for Sections 2
----- and 3.

H. Payload I/F Elements

Install payload I/F elements as required. Include MS, PS, OOS enclosures, mid-body payload I/F's and optional equipment.




FIGURE B-1 HORIZONTAL IVE IN-FIELD ASSEMBLY PROCEDURE

ORIGINAL PAGE IS
OF POOR QUALITY

B-11

SD76-SH-0092




FIGURE B-2 HORIZONTAL IVE IN-FIELD ASSEMBLY PROCEDURE



APPENDIX C

PAYLOAD INTEGRATION BASELINE FUNCTIONAL FLOW BLOCK DIAGRAMS AND OPTIONS



TABLE OF CONTENTS

<u>Paragraph</u>	<u>Title</u>	<u>Page</u>
C.1	Contents.	C-1
C.2	Terminology	C-1
C.3	Payload Integration Analysis -.	C-4
	Functional Flow Block Diagrams and Inter- face Checkout Matrices	



ILLUSTRATIONS

Figure	Title	Page
C-1	Solar Maximum Mission FFBD	C-5
C-2	Solar Physics Dedicated Mission FFBD	C-26
C-3	Module with Pallet (Spacelab) FFBD	C-52
C-4	Large Space Telescope FFBD	C-80
C-5	Mariner Jupiter Orbiter/IUS	C-99

TABLES

Table	Title	Page
C.1	SMM Interface Checkout Matrix	C-13
C.2	Solar Physics Dedicated Mission Interface Checkout Matrix	C-37
C.3	Module with Pallet (Spacelab) Interface Checkout Matrix	C-66
C.4	Large Space Telescope Interface Checkout Matrix	C-88
C.5	Mariner Jupiter Orbiter/IUS Interface Checkout Matrix	C-114



APPENDIX C

PAYLOAD INTEGRATION BASELINE FUNCTIONAL FLOW BLOCK DIAGRAMS AND OPTIONS

C.1 CONTENTS

This appendix contains the detailed descriptions of the payload integration functional flow block diagrams as described in Section 9.0 of the report. A baseline and two optional flows are included for the following five payloads representative of the broad payload spectrum:

1. Solar Maximum Mission
2. Solar Physics Dedicated Mission
3. Module With Pallet (Spacelab)
4. Large Space Telescope
5. Mariner Jupiter Orbiter/IUS

Contents include terminology used, baseline payload integration functional flow block diagrams, and interface checkout matrices identifying differences to the baseline flows for the two options.

C.2 TERMINOLOGY

The following terminology and definitions apply to the data presented in the figures and tables in Section 3, of this appendix:

<u>Cargo</u>	The total complement of payloads carried on any one flight.
<u>Payload</u>	The total complement of specific instruments, space equipment and support hardware carried in the Orbiter to accomplish a certain task in space.
<u>Subsystem</u>	The next functional subdivision of a system.
<u>Assembly</u>	The next functional subdivision of a component (two or more parts or subassemblies).
<u>Subassembly</u>	An assembly within a larger assembly.



<u>Part</u>	A basic element of component, assembly or subassembly.
<u>Acceptance Tests</u>	Acceptance tests are the required formal tests, conducted to demonstrate acceptability of an item for delivery.
<u>Block Numbers in FFBD's</u>	This indicates a sequential number of a block, as shown in the Functional Flow Block Diagram (FFBD) for a given payload processing operation.
<u>Description</u>	Title identification of the blocks in the FFBD's, the functions to be performed, and the operation level (subsystem, system, payload and cargo.)
<u>I/F Knowledge</u>	Four different categories of interface related requirements are reflected. They are as follows: <ol style="list-style-type: none">(1) <u>Orbiter I/F Not Required</u> - This category does not interface with Orbiter:(2) <u>Orbiter I/F Knowledge Required</u> - This category does not interface with Orbiter, but knowledge of Payload/Orbiter interface data is required.



- (3) Direct Orbiter Function Simulated -
In this category some of the Orbiter functions are required to be simulated.
- (4) Direct Orbiter I/F - This category requires that the payload interfaces directly with Orbiter.

Baseline Location Operational site location for the function identified as determined from the NASA payload data base.

Option 1
(User Oriented) Operational site location for the function identified with maximum integration to be accomplished prior to payload delivery to the launch site.

Option 2
Launch site oriented Operational site location for the function identified with maximum integration to be accomplished at the launch site.

GSE Simulators Identifies integration functions requiring usage of IVE or GSE simulators.

IVE Identifies interface functions, in the interface checkout matrix tables that can be accomplished by standardized IVE.

Special Facility A special facility (thermo/vac, vibration or other) is required to perform a given function.

Remarks

Either Site - A given function may be performed at either User or Launch Site. The decision where to perform the function will depend on the results of a trade study of other relevant functions, showing that the chosen site will not affect the operation. However, if the function does not depend on a trade study, it can be performed at the site equipped with the required GSE simulators or IVE, taking into consideration the effects of factors like handling, transportation, risk, availability of personnel etc.



Remarks (Cont)

Both Sites - A given function is to be performed at both sites (User & Launch). Final decision whether the function is to be performed at both sites depends on I/F verification philosophy such as: Whether minimum checkout is performed initially at User site, and maximum checkout at Launch site, or vice versa. Transportation and subsequent checkout and I/F verification requirements will influence the decision.

Trade Study

A study, required to determine the preferable site to perform a given function. Determination of site will depend on evaluation of the factors, presented in the Criteria Table, such as risk, cost, schedule impact, availability of personnel and equipment, etc.

C.3. PAYLOAD INTEGRATION ANALYSIS - FUNCTIONAL FLOW BLOCK DIAGRAMS
AND INTERFACE CHECKOUT MATRICES

The FFBD's and I/F checkout matrix tables are included for the five payloads identified above. These data support the discussion in Section 9.0 of this report. Data presented in Figures C-1 through C-5 and Tables C.1 through C.5 reflect the next level definition of the payload integration processes described in Figure 9-2.




Figure C-1. Solar Maximum Mission FFED

ORIGINAL PAGE IS
OF POOR QUALITY




Figure C-1. Solar Maximum Mission FFBD (Cont)

ORIGINAL PAGE IS
OF POOR QUALITY




Figure C-1. Solar Maximum Mission FFBD (Cont)






Figure C-1. Solar Maximum Mission FFBD (Cont)

ORIGINAL PAGE IS
OF POOR QUALITY



* (1) ORBITER I/F KNOWLEDGE NOT REQUIRED
(2) ORBITER I/F KNOWLEDGE REQUIRED
(3) DIRECT ORBITER FUNCTIONS SIMULATED
(4) DIRECT ORBITER I/F

Figure C-1. Solar Maximum Mission FFBD (Cont)



- * (1) ORBITER I/F KNOWLEDGE NOT REQUIRED
(2) ORBITER I/F KNOWLEDGE REQUIRED
(3) DIRECT ORBITER FUNCTIONS SIMULATED
(4) DIRECT ORBITER I/F

Figure C-1. Solar Maximum Mission FFBD (Cont)

ORIGINAL PAGE
OF POOR QUALITY





Figure C-1. Solar Maximum Mission FFBD (Cont)



* (1) ORBITER I/F KNOWLEDGE NOT REQUIRED
 (2) ORBITER I/F KNOWLEDGE REQUIRED
 (3) DIRECT ORBITER FUNCTIONS SIMULATED
 (4) DIRECT ORBITER I/F

Figure C-1. Solar Maximum Mission FFBD (Cont)

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.1 SMM INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASLINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE CM.	IVE		
1.0	Develop & verify experiments	(2)	User	X					Various sources
1.01	UV magnetograph	(2)		X					
1.02	Extreme UV spectrometer	(2)		X					
1.03	High resolution X-Ray spectrometer	(2)		X					
1.04	Hard X-Ray imaging	(2)		X					
1.05	X-Ray polarimetry	(2)		X					
1.06	Gamma ray detector	(2)		X					
1.07	Hydrogen Alpha photometer	(2)		X					
1.08	Flare finder	(2)		X					
1.1	Experiment acceptance	(1)		X					
1.1.1	UV magnetograph acceptance	(1)		X					
1.1.2	Extreme UV spectrometer acceptance	(1)		X					
1.1.3	H R X R S acceptance	(1)		X					
1.1.4	Hard X-Ray imaging acceptance	(1)		X					
1.1.5	X-Ray polarimetry acceptance	(1)		X					
1.1.6	Gamma ray detector acceptance	(1)		X					
1.1.7	Hydrogen Alpha photometer acceptance	(1)		X					
1.1.8	Flare finder acceptance	(1)		X					
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

Table C.1 (Cont) SSM INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE GIM.	IVE		
1.2	Electrical functional tests	(2)	User	X		X			
1.2.1	UVM electrical functional tests	(2)		X		X			
1.2.2	EUVS electrical functional tests	(2)		X		X			
1.2.3	EXORS electrical functional tests	(2)		X		X			
1.2.4	EXRI electrical functional tests	(2)		X		X			
1.2.5	XRP electrical functional tests	(2)		X		X			
1.2.6	GRD electrical functional tests	(2)		X		X			
1.2.7	HAF electrical functional tests	(2)		X		X			
1.2.8	FF electrical functional tests	(2)		X		X			
1.3	Experiment environmental tests	(2)		X					
1.3.1	Optical performance (vacuum)	(2)		X				X	
1.3.2	Thermal/Vac-thermal balance	(1)		X				X	
1.3.3	Vibration	(1)		X				X	
1.4	Fabricate experiment module structure	(2)		X					
1.4.1	Fabricate electrical harnesses	(1)		X		X			ORB/P/L I/F harnesses included in SSM harnesses
1.4.2	Assemble structural subsystem	(1)		X					
1.5	Assemble experiment module	(1)		X					
1.5.1	Attachment	(1)		X					
1.5.2	Optical alignment	(1)		X					
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.1 (Cont) . BMM INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	OS% SIM.	IVE		
1.6	Experiment module compatibility test	(2)	User	X					
1.6.1	Functional	(2)		X	X	X	X		Trade study (risk, sched., cost)
1.6.2	Thermal/Vac	(1)		X				X	
1.6.3	Vibration	(1)		X				X	
1.6.4	Optical performance	(2)	↓	X	X	X	X		Trade study (risk, sched., cost)
2.0	Develop & verify service system components	(1)	User	X					Various sources
2.01	Transponders	(1)		X					
2.02	Processors	(1)		X					
2.03	Antennas	(1)		X					
2.04	Tape recorders	(1)		X					
2.05	Decoders	(1)		X					
2.06	Relays	(1)		X					
2.07	Telemetry	(1)		X					
2.08	Electronic logic circuits	(1)		X					
2.09	Reaction wheels	(1)		X					
2.10	Sun sensors	(1)		X					
2.11	Solar panels	(1)		X					
2.12	Batteries	(1)	↓	X					↓

* (1) ORBITER I/F NOT REQUIRED

(2) ORBITER I/F KNOWLEDGE REQUIRED

(3) DIRECT ORBITER FUNCTION SIMULATED

(4) DIRECT ORBITER I/F

Table C.1 (Cont) SMM INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITP ORIENTED	OSW SIM.	IVE		
2.13	Thermal blankets	(1)	User	X					Various sources
2.14	Cold gas tankage	(1)		X					
2.15	Regulators	(1)		X					
2.16	Valves	(1)		X					
2.17	Electronic components	(1)		X					
2.18	Deployment mechanisms	(1)		X					
2.19	Miscellaneous equipment	(1)		X					
2.1	Subsystem assembly	(2)		X					
2.1.1	Power switching module	(2)		X					
2.1.2	Thermistor instrumentation	(2)		X					
2.1.3	Caution & warning	(2)		X					
2.1.4	Communications & data handling module	(2)		X					
2.1.5	Power module	(2)		X					
2.1.6	Attitude control subsystem	(2)		X					
2.1.7	Flight support c/o monitoring unit	(2)		X					
2.1.8	Preflight disconnect	(2)		X					
2.1.9	Electrical integration module	(2)		X					
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE 45
OF POOR QUALITY

Table C.1 (Cont) SIM INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASLINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITF ORIENTED	GSE SIM.	IVE		
2.2	Subsystem acceptance	(1)	User	X					
2.2.1	Power switching module acceptance	(1)		X					
2.2.2	Thermistor instrumentation acceptance	(1)		X					
2.2.3	Caution & warning acceptance	(1)		X					
2.2.4	C&DH module acceptance	(1)		X					
2.2.5	Power Module acceptance	(1)		X					
2.2.6	Attitude control subsystem acceptance	(1)		X					
2.2.7	Flt support c/o monitoring unit acceptance	(1)		X					
2.2.8	Preflight disconnect acceptance	(1)		X					
2.2.9	Electrical integration module acceptance	(1)		X					
2.3	Subsystem checkout	(2)		X		X			
2.3.1	Power switching module checkout	(2)		X		X			
2.3.2	Thermistor instrumentation checkout	(2)		X		X			
2.3.3	Caution & warning checkout	(2)		X		X			
2.3.4	C&DH module checkout	(2)		X		X			
2.3.5	Power module checkout	(2)		X		X			
2.3.6	Attitude control subsystem checkout	(2)		X		X			
2.3.7	Flt support c/o monitoring unit checkout	(2)		X		X			
2.3.8	Preflight disconnect checkout	(2)		X		X			
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

Table C.1 (Cont) SSM INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
2.3.9.	Electrical integration module checkout	(2)	User	X		X			
2.4	Fabricate SSM structure	(2)		X					
2.4.1	Fabricate electrical harnesses	(2)		X		X			ORB/P/L I/F knowledge for I/F Harnesses
2.4.2	Assemble structural subsystem	(1)		X					
2.5	Assemble service system module	(1)		X					
2.6	Software verification	(2)		X		X			Can be accomplished at remote locat
2.6.1	Checkout software	(2)		X					
2.6.2	Applications software	(2)		X					
2.6.3	Computers and processors	(2)		X					
2.6.4	Test procedures	(2)		X					
2.7	SSM functional test	(2)		X	X	X	X		To be accomplished at both sites
2.7.1	Power switching module checkout	(2)		X	X	X	X		
2.7.2	Thermistor instrumentation checkout	(2)		X	X	X	X		
2.7.3	Caution & warning checkout	(2)		X	X	X	X		
2.7.4	C&DH module checkout	(2)		X	X	X	X		
2.7.5	Power module checkout	(2)		X	X	X	X		
2.7.6	Attitude control system checkout	(2)		X	X	X	X		
2.7.7	Flt support c/o monitoring unit checkout	(2)		X	X	X	X		
2.7.8	Preflight disconnect checkout	(2)		X	X	X	X		
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

C-19

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	G99 TIM.	IVE		
2.7.9	Electrical integration module checkout	(2)	User	X	X	X	X		At either or both sites
2.8	Environmental test	(1)		X		X			
2.8.1	Vibration/acoustics	(1)		X		X		X	
2.8.2	Thermal balance	(1)		X		X		X	
3.0	Integration of subsystem modules	(2)		X	X	X	X		Trade study
3.1	EM/SSM electrical integration	(1)		X					Connect cables-no power
3.2	EM/SSM electrical functional tests	(2)		X	X	X	X		Trade study
3.3	EM/SSM mechanical integration	(1)		X					
3.3.1	Mechanically mate EM & SSM	(1)		X	X	X	X		Trade study
3.3.2	Connect modules electrically	(1)		X	X	X	X		
3.4	Perform EM/SSM interface verification tests	(2)		X	X	X	X		
3.4.1	Module to module continuity	(1)		X	X	X	X		
3.4.2	Bus isolation check	(1)		X	X	X	X		
3.4.3	Fitting leak check	(1)		X	X	X	X		
3.4.4	Repeat of electrical functional tests	(2)		X	X	X	X		At either or both sites
3.4.5	Mechanical fit check	(2)		X	X	X	X		

* (1) ORBITER I/F NOT REQUIRED

(2) ORBITER I/F KNOWLEDGE REQUIRED

(3) DIRECT ORBITER FUNCTION SIMULATED

(4) DIRECT ORBITER I/F

Table C.1 (Cont) SMM INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	G98 SIM.	IVE		
4.0	Prepare to initiate payload operations	(2)	User	X	X				
4.01	Test readiness briefings	(1)		X	X				
4.02	Review test procedures	(1)		X	X				Both sites
4.03	Review hardware documentation	(2)		X	X				
4.04	Review safety plans	(1)		X	X				
4.05	Review interface documentation	(2)		X	X				
4.06	Checkout & calibrate test equipment	(1)		X	X	X	X		
4.1	Perform SMM integrated system tests	(1), (2), (3)		X	X	X	X		
4.1.1	Functional & electrical performance	(2)		X	X	X	X		
4.1.2	EMC/RFI tests	(2)		X	X				Monitor EMI/RFI during funct. tests
4.1.3	Mass property determination	(1)		X				X	Special facility
4.1.4	Optical alignment	(2)		X	X	X	X		Both sites
4.1.5	Thermal/vac balance	(1)		X		X		X	Special facility required
4.1.6	Antenna pattern	(2)		X	X	X	X		Both sites
4.1.7	BTDR/TDRSS compatibility	(3)		X	X				Direct link communications
4.1.8	Fine pointing	(2)		X	X	X	X		Both sites
4.1.9	Vibration/shock/acoustics	(1)		X	X	X		X	Special facility required
4.1.10	Deployment	(2)		X	X	X	X		
4.1.11	Magnetics	(2)		X		X			
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.1 (Cont)

SMM INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
5.0	Configure for flight	(1)	User	X	X				Either site (trade study)
5.01	Inspect	(1)		X	X				
5.02	Refurbish	(1)		X	X				
5.03	Install solar panels & external equipment	(1)		X	X				
5.1	Closout, package & ship to launch site	(1)		X					
5.1.1	Install access panels	(1)		X					
5.1.2	Paint	(1)		X					
5.1.3	Emissivity tests	(1)		X					
5.1.4	Install in shipping container	(1)		X					
5.1.5	Add environment monitoring sensors	(1)		X					
5.1.6	Install shipping support equipment	(1)		X					
5.1.7	Ship	(1)		X					
6.0	SMM arrival at launch site	(1)	Launch St.		X				
6.1	Transfer to receiving facility	(1)			X				
6.2	Perform receiving inspection operations	(1)			X				
6.3	Perform individual experiment checkout	(1)			X	X	X		Post shipping requirement
6.3.1	UV magnetograph checkout	(1)			X	X	X		
6.3.2	Extreme UV spectrometer checkout	(1)			X	X	X		
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

Table C.1 (Cont) SMN INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITTING ORIENTED	GSE TIM.	IVE		
6.3.3	High resolution X-Ray spectrometer checkout	(1)	Launch Site		X	X	X		Post shipping requirement
6.3.4	Hard X-Ray imaging checkout	(1)			X	X	X		
6.3.5	X-Ray polarimetry checkout	(1)			X	X	X		
6.3.6	Gamma ray detector checkout	(1)			X	X	X		
6.3.7	Hydrogen Alpha photometer checkout	(1)			X	X	X		
6.3.8	Flare finder checkout	(1)			X	X	X		
6.4	Perform individual subsystem checkout	(1)			X	X	X		
6.4.1	Power switching module checkout	(1)			X	X	X		
6.4.2	Thermistor instrumentation checkout	(1)			X	X	X		
6.4.3	Caution & warning module checkout	(1)			X	X	X		
6.4.4	C&DH module checkout	(1)			X	X	X		
6.4.5	Power module checkout	(1)			X	X	X		
6.4.6	Attitude control system checkout	(1)			X	X	X		
6.4.7	Flt support c/o monitoring unit checkout	(1)			X	X	X		
6.4.8	Preflight disconnect checkout	(1)			X	X	X		
6.4.9	Electrical integration module checkout	(1)			X	X	X		
7.0	Perform combined system test	(2), (3)		X	X	X	X		7.0, 8.1, & 9.0 tests could be combined & tests conducted in IVE. Need trade study.
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.1 (Cont) SSM INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
8.0	Transfer to special test facility	(1)	Launch Site		X	X	X		7.0, 8.1 & 9.0 tests could be combined & tests conducted in IVE. Need trade study
8.1	Perform special S/C test	(2), (3)			X	X	X		
8.1.1	Countdown and liftoff simulation	(2), (3)			X	X	X		
8.1.2	Ascent simulation	(2), (3)			X	X	X		
8.1.3	On orbit deployment simulation	(2), (3)			X	X	X		
8.1.4	On orbit operations simulation	(2), (3)			X	X	X		
8.1.5	Retrieval simulation	(2), (3)			X	X	X		
8.1.6	Descent simulation	(2), (3)			X	X	X		
8.1.7	Landing simulation	(2), (3)			X	X	X		
9.0	Transfer to orbiter integration facility	(1)			X				O & C (MSOB)
9.01	Install GSE interface simulators	(2)		X	X	X	X		Orbiter simulator required
9.1	Perform cargo/orbiter integration test	(3)		X	X	X	X		7.0, 8.1, & 9.0 tests could be combined & tests conducted in IVE. Need trade study for cost effectiveness
9.1.1	Fit check cargo to orbiter interface	(3)		X	X	X	X		
9.1.2	Verify compatibility of command & data X-fer at orbiter/cargo interface	(3)		X	X	X	X		
9.1.3	Verify caution & warning operation	(3)		X	X	X	X		
9.1.4	Verify operation of PS equipment	(3)		X	X	X	X		User site could be used if Orbiter Simulator is available
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

C-2A

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
9.2	Perform tear down operations	(1)	Launch Site	X	X	X	X		User site could be used if orbiter simulator is available
9.2.1	Remove from simulators	(1)		X	X	X	X		
9.2.2	Secure integration facility	(1)		X	X	X	X		
9.2.3	Inspect & repair SMM, as applicable	(1)		X	X	X	X		
10.0	Perform weight & balance operations	(1)		X	X			X	Specialized facility required
11.0	Transfer to OFF	(1)			X				
11.1	Install cargo in orbiter	(4)			X				
11.2	Perform cargo to orbiter I/F verification ops.	(4)			X				
11.2.1	Plugs out continuity check	(1)			X				
11.2.2	Connect electrical cables & verify	(4)			X				
11.2.3	Connect fluid lines & verify	(4)			X				
11.2.4	Connect all umbilicals & verify	(4)			X				
11.2.5	Verify all mechanical attachments	(4)			X				
11.3	Payload bay final closeout	(4)			X				
11.3.1	Service SMM with consumables	(4)			X				
11.3.2	Install pyrotechnic devices	(4)			X				
11.3.3	Replace flight covers & caps	(4)			X				


* (1) ORBITER I/F NOT REQUIRED

(2) ORBITER I/F KNOWLEDGE REQUIRED

(3) DIRECT ORBITER FUNCTION SIMULATED

(4) DIRECT ORBITER I/F

[illegible][illegible]



ORIGINAL PAGE
OF POOR QUALITY




Figure C-2 Solar Physics Dedicated Mission FFBD (Cont)




Figure C-2 Solar Physics Dedicated Mission FFBD (Cont)




Figure C-2 Solar Physics Dedicated Mission FFBD (Cont)




Figure C-2 Solar Physics Dedicated Mission FFBD (Cont)

ORIGINAL PAGE IS
OF POOR QUALITY




Figure C-2 Solar Physics Dedicated Mission FFBD (Cont)




Figure C-2 Solar Physics Dedicated Mission FFBD (Cont)

ORIGINAL PAGE IS
OF POOR QUALITY




Figure C-2 Solar Physics Dedicated Mission FFBD (Cont)




Figure C-2 Solar Physics Dedicated Mission FFBD (Cont)




Figure C-2 Solar Physics Dedicated Mission FFBD (Cont)




Figure C-2 Solar Physics Dedicated Mission FFBD (Cont)

Table C.2 Solar Physics Dedicated Mission Interface Checkout Matrix

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE TIM.	IVE		
1.0	Develop & verify experiments	(2)	User	X					Various sources
1.1	Experiments	(2)		X					
1.1.1	100 cm photoheliograph	(2)		X					
1.1.2	UV spectrograph	(2)		X					
1.1.3	Extreme UV spectro heliometer	(2)		X					
1.1.4	Spectrometer/spectro heliograph	(2)		X					
1.1.5	Soft X-Ray telescope/spectrograph	(2)		X					
1.1.6	Soft X-Ray spectrometer/spectro heliograph	(2)		X					
1.1.7	Grid collimator acquisition photometer	(2)		X					
1.1.8	Hard X-Ray imaging	(2)		X					
1.1.9	X-Ray continuum spectrometry	(2)		X					
1.1.10	X-Ray burst detector	(2)		X					
1.1.11	X-Ray/gamma ray spectrometer	(2)		X					
1.1.12	Gamma ray spectrometer	(2)		X					
1.1.13	Solar X-Ray polarimeter	(2)		X					
1.1.14	Bragg reflection crystal polarimeter	(2)		X					
1.1.15	Solar neutron experiment	(2)		X					
1.1.16	High energy gamma ray & neutron detector	(2)		X					
1.1.17	Externally occulted coronagraph	(2)		X					
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

Table C.2 Solar Physics Dedicated Mission Interface Checkout Matrix (Cont)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	99% SIM.	IVE		
1.2	Experiment acceptance	(1)	User	X					
1.2.1 through 1.2.17	experiments, same as in (1.1) are acceptance tested	(1)		X					
1.3	Experiment functional tests	(2)		X					
1.3.1 through 1.3.17	experiments, same as in (1.1) are individually checked out	(2)		X		X			
1.4	Prepare & transfer to User facility	(1)		X					
1.5	Receive & inspect	(1)		X					
1.5.1	Inspect for damage	(1)		X					
1.5.2	Check environmental monitors	(1)		X					
1.5.3	Check environmental protection enclosures	(1)		X					
1.5.4	Review documentation	(1)		X					
1.6	Transfer to assembly & checkout facility	(1)		X					
2.0	Develop & verify support equipment	(2)		X					
2.1	Support equipment	(2)		X					
2.1.1	Control & display assembly	(2)		X					
2.1.2	Control & display electronics	(2)		X					
2.1.3	Tape recorder & magazine	(2)		X					
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

Table C.2 Solar Physics Dedicated Mission Interface Checkout Matrix (Cont)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
2.1.4	Hydrogen Alpha monitor	(2)	User	X					
2.1.5	Purge gas subsystem	(2)		X					
2.2	Support equipment acceptance	(1)		X					
2.2.1 through 2.2.5	support subsystems, same as in (2.1)	(1)		X					
	are acceptance tested								
2.3	Support equipment functional test	(2)		X		X			
2.3.1 through 2.3.5	support subsystems, same as in (2.1)	(2)		X		X			
	are individually checked out								
2.4	Prepare and transfer to User facility	(1)		X					
2.5	Receive & inspect	(1)		X					
2.5.1	Inspect for damage	(1)		X					
2.5.2	Check environmental monitors	(1)		X					
2.5.3	Check environmental protection enclosures	(1)		X					
2.5.4	Review documentation	(1)		X					
2.6	Transfer to assembly and checkout facility	(1)		X					
2.7	Pallet mounted support equipment (unpressurized)	(1)		X					
2.7.1	Hydrogen Alpha monitor	(1)		X					
2.7.2	Purge gas subsystem	(1)		X					
2.7.3	Payload station equipment	(1)		X					
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

C-40

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITP ORIENTED	GSE SIM.	IVE		
2.8	Experiment igloo equipment (pressurized)	(1)	User	X					
2.8.1	Control & display electronics	(1)		X					
2.8.2	Control & display assembly	(1)		X					
2.8.3	Tape recorder and magazine	(1)		X					
3.0	Receive pallet & experiment igloo (return of post flight hardware)	(1)		X					
3.1	Refurbish pallet & igloo	(1)		X					
3.1.1	Service cooling loops	(1)		X					
3.1.2	Functional check of power conditioning equip.	(1)		X					
3.1.3	Remove all harnesses	(1)		X					
3.1.4	Inspect & repair applicable harnesses	(1)		X					
3.1.5	Remove non applicable brackets	(1)		X					
3.1.6	Examine mating surfaces	(1)		X					
3.1.7	Paint	(1)		X					
3.1.8	Emissivity test	(1)		X					
3.2	Prepare & transfer to User facility	(1)		X					
3.3	Receive & inspect	(1)		X					
3.3.1	Check ID & damage	(1)		X					

* (1) ORBITER I/F NOT REQUIRED

(2) ORBITER I/F KNOWLEDGE REQUIRED

(3) DIRECT ORBITER FUNCTION SIMULATED

(4) DIRECT ORBITER I/F

1

Table C.2 Solar Physics Dedicated Mission Interface Checkout Matrix (Cont)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITP ORIENTED	GSE SIM.	IVE		
3.3.2	Review history	(1)	User	X					
3.4	Transfer to assembly & checkout facility	(1)		X					
3.5	Remove experiment support igloo	(1)		X					
3.6	Configure igloo structure for support equip.	(1)		X					
3.6.1	Install brackets	(1)		X					
3.6.2	Install equipment platforms	(1)		X					
3.6.3	Install pressure lines	(1)		X					
3.6.4	Leak check	(1)		X					
3.7	Install basic equipment in pallet	(1)		X					
3.7.1	Harnesses	(1)		X					
3.7.2	Purge lines	(1)		X					
3.7.3	Cooling lines	(1)		X					
4.0	Complete assembly of experiment support igloo	(1)		X					
5.0	Modify pallet to flight configuration	(2)		X					
5.1	Install platforms and brackets	(1)		X					
5.2	Install gimbal mounts	(1)		X					
5.3	Install mech. & electr. connect panels	(2)		X					

* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED
 (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F

Table C.2 Solar Physics Dedicated Mission Interface Checkout Matrix (Cont)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
5.4	Install purge manifolds	(1)	User	X					
5.5	Install LM2 coolant loops	(1)		X					
6.0	Install experiments on pallet	(1)		X					
6.1	Install experiment igloo on pallet	(1)		X					
6.2	Install support equipment	(1)		X					
6.3	Verify integrity of individual assemblies	(1)		X					
6.3.1	Electrical bonding check	(1)		X					
6.3.2	Mechanical alignment check	(1)		X					
6.3.3	Flugs out continuity	(1)		X					
6.4	Interface connection & verification	(1)		X					
6.4.1	Mate & check interface connectors	(1)		X					
6.4.2	Connect fluid line I/F fittings & leak check	(1)		X					
6.4.3	Check end to end continuity of cabling	(1)		X					
6.4.4	End to end leak check of fluid systems	(1)		X					
6.5	GSE & simulators checkout	(1)		X	X	X	X		Trade study
6.5.1	Check simulators/GSE/facility interfaces	(1)		X	X	X	X		
6.5.2	Perform test readiness checkout	(1)		X	X	X	X		
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE 133
OF 1000 QUALITY

Table C.2 Solar Physics Dedicated Mission Interface Checkout Matrix (Cont)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
7.0	Mate flight equipment with GSE/simulators	(1)	Use	X	X	X	X		Trade study
7.1	Support igloo	(1)		X	X	X	X		
7.2	Payload station equipment	(1)		X	X	X	X		
7.3	Pallet & experiments	(1)		X	X	X	X		
8.0	Pre-power interface verification tests	(1)		X	X	X	X		
8.1	Verify mechanical attachments	(1)		X	X	X			
8.2	Verify electrical continuity	(1)		X	X	X	X		
8.3	Leakage check	(1)		X	X	X			
8.4	Bus isolation check	(1)		X	X	X			
8.5	Check flow through coolant loops	(1)		X	X	X	X		
8.6	Check pre-power switch positions	(1)		X	X	X	X		
9.0	Power-up interface verification tests	(2)		X	X	X	X		
9.1	Power-up elect. subsystems individually	(1)		X	X	X	X		
9.2	Determine power distribution	(2)		X	X	X	X		
9.3	Verify Caution & warning indicators	(2)		X	X	X	X		
9.4	Power-up control console	(1)		X	X	X	X		
9.5	Power-up computer facility	(1)		X	X	X	X		
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

Table C.2 Solar Physics Dedicated Mission Interface Checkout Matrix (Cont)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	G9R SIM.	IVE		
9.6	Verify facility ready for data processing	(1)	User	X	X	X	X		Trade study
9.7	Verify auxiliary equipment operating	(1)		X	X	X	X		
10.0	Individual experiment verification	(2)		X	X	X	X		
10.1	Deployment mechanism operation	(2)		X	X	X			
10.2	Verify controls & displays	(2)		X	X	X	X		Trade study
10.3	Operation of experiment sensors	(2)		X	X	X	X		
10.4	Operation of control & display electronics	(2)		X	X	X	X		
10.5	Verify all flt support equipment operating	(2)		X	X	X	X		
11.0	Integrated experiment tests	(2), (3)		X	X	X	X		Both sites; trade study
11.1	Mission sim. test with experiments operating	(3)		X	X	X	X		
11.2	Integrated experiment deployment	(2)		X	X	X	X		
12.0	EMC/RFI tests (EMC/RFI monitored during operation of experiments & flight support equipment)	(2)		X	X	X	X		
13.0	Data review & retest, if required	(1)		X	X	X	X		
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE IS
POOR QUALITY

ASIAN 600 SPACE PHYSICS DESIGNER MISSION INTERFACE CHECKOUT MATRIX (CONT.)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
14.0	Secure GSE & simulators	(1)	User	X	X	X	X		Either site
14.1	Disconnect GSE	(1)		X	X	X	X		
14.2	Disconnect & cap coolant lines	(1)		X	X	X	X		
14.3	Remove electrical connectors	(1)		X	X	X	X		
15.0	Post-test examination	(1)		X	X				
15.1	Examine experiments/pallet/experiment igloo	(1)		X	X				
15.2	Clean & repair, as necessary	(1)		X	X				
15.3	Load non-hazardous supplies	(1)		X	X				
16.0	Closeout, package & ship to Launch Site	(1)		X					
16.1	Closeout & seal experiments	(1)		X					
16.2	Paint as required	(1)		X					
16.3	Emissivity test	(1)		X					
16.4	Install transportation servicing equipment	(1)		X					
17.0	Pallet/exper./flt. support equip. arr. GTS	(1)	Launch site		X				
17.1	Transfer to receiving facility	(1)			X				
17.2	Perform receiving inspection operations	(1)			X				
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

Table C.2 Solar Physics Dedicated Mission Interface Checkout Matrix (Cont)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
17.3	Transfer to integration facility	(1)	Launch site	X	X				
18.0	Refurbished support system igloo arrival at Launch Site	(1)			X				
18.1	Transfer to receiving facility	(1)			X				
18.2	Perform receiving inspection operations	(1)			X				
18.3	Transfer to integration facility	(1)			X				
19.0	Perform mating operations	(1)			X				
19.1	Interface verification	(1)			X	X			
19.1.1	End to end electrical continuity check	(1)			X	X	X		
19.1.2	Verify alignment	(1)			X	X			
19.1.3	Interface continuity check	(1)			X	X			
19.1.4	Leak check fluid lines	(1)			X	X			
20.0	Prepare payload interface GSE	(1)		X	X	X	X		Either site
20.1	Move to integration facility	(1)		X	X	X	X		
20.2	Configure for experiment support	(1)		X	X	X	X		
20.3	Connect facility fluid lines	(1)		X	X	X	X		
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE
OF FOUR

Table C.2 Solar Physics Dedicated Mission Interface Checkout Matrix (Cont)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
20.4	Connect facility electrical harness	(1)	Launch site	X	X	X	X		Either site
21.0	Verify operation of payload/GSE interface	(2)		X	X	X	X		
21.1	Fuel cell/power distribution simulation	(2)		X	X	X	X		
21.2	Orbiter signal simulation	(2)		X	X	X	X		
21.3	Payload specialist station equipment operation	(2)		X	X	X	X		
21.4	Verify umbilical interfaces	(2)		X	X	X	X		
21.5	Verify oper. of data management subsystems	(2)		X	X	X	X		
21.6	Verify oper. of computer periph. equipment	(1)		X	X	X	X		
21.7	Verify operation of operator console	(1)		X	X	X	X		
22.0	Mate payload & interface GSE	(2)		X	X	X	X		Either site; trade study
22.1	Pre-power interface verification	(2)		X	X	X	X		
22.1.1	Verify payload/GSE mech., elect. & fluid I/F	(1)		X	X				
22.1.2	Perform bus isolation tests	(1)		X	X	X	X		
22.1.3	Conduct pre-power switch list	(2)		X	X	X	X		
22.1.4	Check operation of all caution & warning	(2)		X	X	X	X		
22.2	Power-up functional checkout	(2),(3)		X	X	X	X		
22.2.1	Monitor bus voltages & current	(2)		X	X	X	X		
22.2.2	Monitor coolant flow	(2)		X	X	X	X		
22.2.3	Check power distribution	(2)		X	X	X	X		
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

Table C.2 Solar Physics Dedicated Mission Interface Checkout Matrix (Cont.)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
22.2.4	Initiate computer self-checks	(1)	Launch site	X	X	X	X		Either site; trade study
22.2.5	Conduct command & control test	(2)		X	X	X	X		
22.2.6	Evaluate computer peripheral equipment	(2)		X	X	X	X		
22.2.7	Functional c/o of support systems and experiment equipment interfaces	(3)		X	X	X	X		
22.2.8	Evaluate manual emergency backup modes	(3)		X	X	X	X		
23.0	Data review	(2)		X	X				Trade study, sec 22.2
24.0	Remove and secure interface GSE	(1)		X	X	X	X		
25.0	Close-out operations	(1)			X				
25.1	Load non-hazardous supplies	(1)			X				
25.2	Install access panels & cover plates	(1)			X				
25.3	Touch-up paint	(1)			X				
25.4	Emissivity test	(1)			X				
26.0	Pressure decay leak check	(1)			X				
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

Table C.2 Solar Physics Dedicated Mission Interface Checkout Matrix (Cont)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
27.0	Weight & balance test	(1)	Launch site		X			X	
28.0	Transfer to OFF	(1)			X				
29.0	Prepare cargo for mating with orbiter	(2)			X				
29.1	Inspect interface connectors	(2)			X				
29.2	Service with non-hazardous materials	(1)			X				
29.3	Install flight batteries and chargers	(1)			X				
30.0	Install payload control & support equip. in Orb.	(4)			X				
30.1	Install cargo in orbiter payload bay	(4)			X				
31.0	Orbiter/cargo interface verification test	(4)			X				
31.1	Plugs out electrical continuity	(1)			X				
31.2	Connect & verify umbilicals & fluid lines	(4)			X				
31.3	Install & verify wash, latches & retention dev.	(4)			X				
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

1
RIGINATI PAGE IS
A POOR QUALITY

C-50




Figure C-3 Module with Pallet (Spacelab)

- (1) ORBITER I/F NOT REQUIRED
- (2) ORBITER I/F KNOWLEDGE REQUIRED
- (3) DIRECT ORBITER FUNCTIONS SIMULATED
- (4) DIRECT ORBITER I/F




Figure C-3 Module with Pallet (Cont)

ORIGINAL PAGE IS
OF POOR QUALITY






Figure C-3 Module with Pallet (Cont)




- (1) ORBITER I/F NOT REQUIRED
- (2) ORBITER I/F KNOWLEDGE REQUIRED
- (3) DIRECT ORBITER FUNCTIONS SIMULATED
- (4) DIRECT ORBITER I/F

Figure C-3 Module with Pallet (Cont)


ORIGINAL PAGE IS
OF POOR QUALITY






- (1) ORBITER I/F NOT REQUIRED
- (2) ORBITER I/F KNOWLEDGE REQUIRED
- (3) DIRECT ORBITER FUNCTIONS SIMULATED
- (4) DIRECT ORBITER I/F

Figure C-3 Module with Pallet (Cont)



- (1) ORBITER I/F NOT REQUIRED
 (2) ORBITER I/F KNOWLEDGE REQUIRED
 (3) DIRECT ORBITER FUNCTIONS SIMULATED
 (4) DIRECT ORBITER I/F


Figure C-3 Module with Pallet (Cont)



- (1) ORBITER I/F NOT REQUIRED
(2) ORBITER I/F KNOWLEDGE REQUIRED
(3) DIRECT ORBITER FUNCTIONS SIMULATED
(4) DIRECT ORBITER I/F


Figure C-3 Module with Pallet (Cont)

ORIGINAL PAGE IS
OF POOR QUALITY



- (1) ORBITER I/F NOT REQUIRED
- (2) ORBITER I/F KNOWLEDGE REQUIRED
- (3) DIRECT ORBITER FUNCTIONS SIMULATED
- (4) DIRECT ORBITER I/F

Figure C-3 Module with Pallet (Cont)



- (1) ORBITER I/F NOT REQUIRED
(2) ORBITER I/F KNOWLEDGE REQUIRED
(3) DIRECT ORBITER FUNCTIONS SIMULATED
(4) DIRECT ORBITER I/F

Figure C-3 Module with Pallet (Cont)

ORIGINAL PAGE IS
OF POOR QUALITY




Figure C-3 Module with Pallet (Cont)

- (1) ORBITER I/F NOT REQUIRED
- (2) ORBITER I/F KNOWLEDGE REQUIRED
- (3) DIRECT ORBITER FUNCTIONS SIMULATED
- (4) DIRECT ORBITER I/F




Figure C-3 Module with Pallet (Cont)

- (1) ORBITER I/F NOT REQUIRED
- (2) ORBITER I/F KNOWLEDGE REQUIRED
- (3) DIRECT ORBITER FUNCTIONS SIMULATED
- (4) DIRECT ORBITER I/F

ORIGINAL PAGE IS
OF POOR QUALITY




Figure C-3 Module with Pallet (Cont)




Figure C-3 Module with Pallet (Cont)

- (1) ORBITER I/F NOT REQUIRED
- (2) ORBITER I/F KNOWLEDGE REQUIRED
- (3) DIRECT ORBITER FUNCTIONS SIMULATED
- (4) DIRECT ORBITER I/F

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.3 MODULE WITH PALLET (SPACE)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	NOTES
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITP ORIENTED	GSE SIM.	IVE		
1.0	Racks and rack sets	(2)	User	X					Various sources
1.1	Structure	(2)		X					
1.2	Mounting brackets	(1)		X					
1.3	Cables	(1)		X					
2.0	Racks experiments & support equipment	(1)		X					
3.0	Pallet experiments & support equipment	(1)		X					
4.0	Pallet	(2)		X					
4.1	Structure	(2)		X					
4.2	Mounting brackets	(1)		X					
4.3	Cables	(1)		X					
5.0	Receive racks & rack sets	(1)		X					
5.1	Inspect for shipping damage	(1)		X					
6.0	Receive racks experiments & support equipment	(1)		X					
6.1	Inspect for shipping damage	(1)		X					

* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED

(2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F

Table C.3 (Cont) MODULE WITH PALLET (SPACELAB)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
7.0	Receive pallet experiments & support equipment	(1)	User	X					Various sources
7.1	Inspect for shipping damage	(1)		X					
8.0	Receive pallet	(1)		X					
8.1	Inspect for shipping damage	(1)		X					
9.0	Mate racks and experiments	(1)		X					
9.1	Validate experiment/rack interface	(1)		X					
9.1.1	Continuity of electrical connections	(1)		X					
9.1.2	Leak check fluid connections	(1)		X					
9.1.3	Alignment check	(1)		X					
9.2.	Transfer to integration site (user)	(1)		X					
10.0	Mate pallet and experiments	(1)		X					
10.1	Validate experiment/pallet interface	(1)		X					
10.1.1	Continuity of electrical connections	(1)		X					
10.1.2	Leak check of fluid connections	(1)		X					
10.1.3	Alignment check	(1)		X					
10.2	Transfer to integration site	(1)		X					
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

Table C.3 (Cont) MODULE WITH PALLET (SPACELAB)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSS SIM.	IVE		
11.0	Receive & inspect experiments/racks	(1)	User	X					
12.0	Receive & inspect experiment/pallet	(1)		X					
13.0	Prepare assembly stand	(1)		X					
14.0	Receive & inspect additional rack sets & floor	(1)		X					
15.0	Install racks, pallets, experiments in assembly stand & validate	(1)		X					
15.1	Plugs out continuity	(1)		X					
15.2	Mate connectors and fittings	(1)		X					
15.3	Leak check fluid fittings	(1)		X					
16.0	Receive and inspect aft bulkhead	(1)		X					
17.0	Install aft bulkhead in assembly stand	(1)		X					
17.1	Leak check fluid fittings	(1)		X					
17.2	Verify electrical continuity at bulkh. conn.	(1)		X					
<div> <div> (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED </div> <div> (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F </div> </div>									

Table C.3 (Cont)

MODULE WITH PALLET (SPACELAB)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASLINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITF ORIENTED	GSE SIM.	IVE		
18.0	Pre-integration of individual experiments	(1)	User	X	X				Unique C/O equipment required. Either site: trade study.
19.0	Integration test GSE preparation	(1)		X	X	X			Either site.
19.1	Orbiter simulation set	(1)		X	X	X			
19.2	Support system simulator	(1)		X	X	X			
19.3	PS station simulator	(1)		X	X	X			
19.4	Auxiliary GSE	(1)		X	X	X			
20.0	Perform remaining mating & verif. requirements	(1)		X	X				Either site: trade study
21.0	Integration test GSE checkout	(1)		X	X				Either site.
21.1	Coolant loop operation	(1)		X	X				
21.2	Bus isolation test	(1)		X	X				
21.3	Switch position checkout	(1)		X	X				
21.4	Power distribution	(1)		X	X				
21.5	Caution & warning operation	(1)		X	X				
22.0	Move to integration test site	(1)		X	X				Either site
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.3 (Cont) MODULE WITH PALLET (SPACELAB)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASLINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
23.0	Checkout computer segment of GSE	(1)	User	X	X				Either site
23.1	Console operation	(1)		X	X				
23.2	Computer/instrumentation selfcheck	(1)		X	X				
23.3	Verify command/control capability	(1)		X	X				
24.0	Receive & inspect PS panels	(1)		X	X				
25.0	Install PS panels in GSE	(1)		X	X				
26.0	Mate payload and integration test GSE	(1)		X	X				
27.0	Perform GSE/payload interface c/o tests	(1)		X	X	X	X		Either site; trade study
27.1	Verify simulator/racks/pallet interfaces	(1)		X	X	X	X		
27.2	Check control loops flow control	(1)		X	X	X	X		
28.0	Perform subsystem verification tests	(2)		X	X	X	X		Trade study
28.1	Bus isolation verification	(1)		X	X	X	X		
28.2	Determine power distribution	(2)		X	X	X	X		
28.3	Verify caution & warning circuitry	(2)		X	X	X	X		
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

Table C.3 (Cont) MODULE WITH PALLET (SPACELAB)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
28.4	Perform computer & instrumentation selfchecks	(2)	User	X	X	X	X		Trade study
28.5	Verify data management subsystem com. & control	(1)		X	X	X	X		
28.6	Verify operation of peripheral equipment	(1)		X	X	X	X		
28.7	Verify compatibility with ground data base	(2)		X	X	X	X		
28.8	Verify operation of auxiliary equipment	(1)		X	X	X	X		
29.0	Load and verify integrated software	(2)		X	X	X	X		Either site
29.1	Verify capability to send/receive data messages	(2)		X	X	X	X		
29.2	Verify capability to perform service routines	(2)		X	X	X	X		
30.0	Individual experiment checkout	(1)		X	X				Unique experiment equipment
30.1	Navigation	(1)		X	X				
30.2	Earth observation	(1)		X	X				
30.3	Environmental effects	(1)		X	X				
30.4	Components & systems	(1)		X	X				
30.5	Microbiology	(1)		X	X				
30.6	Physics and chemistry	(1)		X	X				
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.3 (Cont) MODULE WITH PALLET (SPACELAB)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SIFT ORIENTED	GSE SIM.	IVE		
31.0	Integrated subsystem tests	(2)	User	X	X	X	X		Trade study
31.1	Activate control and displays	(1)		X	X	X	X		
31.2	Activate support equipment	(1)		X	X	X	X		
31.3	Monitor C&D console during subsequent tests	(2)		X	X	X	X		
31.4	Verify operation of pallet-mtd deployable experiment equipment	(2)		X	X	X	X		
31.5	Verify operation of rack-mtd mechanical experiment equipment	(2)		X	X	X	X		
31.6	Verify functional operation of experiments/support equipment	(2)		X	X	X	X		
31.7	Verify data processing/recording equipment	(2)		X	X	X	X		
32.0	EMC/RFI determination	(1)		X	X				Special equipment required
33.0	Data review and evaluation	(2)		X	X				Can be accomplished anywhere
34.0	De-mate payload & GSE	(1)		X	X				
34.1	Remove payload station panels	(1)		X	X				
34.2	Secure integration test GSE	(1)		X	X				
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

Table C.3 (Cont) MODULE WITH PALLET (SPACELAB)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
35.0	Stow non time-critical items	(1)	User	X	X				Either site
36.0	Prepare & transfer P/L station panels & util. harness	(1)		X	X				↓
37.0	Prepare & transfer racks/experiments/pallets	(1)		X	X				
38.0	R & I payload station panels & utility harness	(1)		X	X				
39.0	R & I racks/pallets/experiments	(1)	↓	X	X				
40.0	Refurbish SM & extension module shells	(1)	Launch site		X				
40.1	Transfer SM & extension module shells	(1)			X				
40.2	R & I SM & extension module shells	(1)			X				
41.0	Refurbish FS equipment & experiments	(1)			X				
41.1	Transfer FS equipment & experiments	(1)			X				
41.2	R & I refurbished FS equipment & experiments	(1)			X				
42.0	Install racks/pallets/experiments in assay stand	(1)			X				
43.0	Prepare integration test GSE	(2)		X	X	X	X		Either site; trade study
43.1	Orbiter electrical I/F simulators	(2)		X	X	X	X		
43.2	Orbiter mechanical I/F simulators	(2)		X	X	X	X		
43.3	Servicing units	(1)		X	X	X	X		
43.4	Facility I/F equipment	(1)		X	X	X	X		
43.5	Payload station simulator	(2)		X	X	X	X		↓
44.0	Mtc experiment train with module shells	(1)	↓	X	X				Either site
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

Table C.3 (Cont) MODULE WITH PALLET (SPACELAB)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
45.0	Install P/L station panels & utility Harness in GSE	(2)	Launch site	X	X				Either site
46.0	Install refurbished FS equipment & experiments	(1)			X				
47.0	Integration GSE checkout	(2)		X	X	X	X		Either site
47.1	Fuel cell/power distribution simulation	(2)		X	X	X	X		
47.2	Orbiter signal distribution	(2)		X	X	X	X		
47.3	Payload station equipment	(2)		X	X	X	X		
47.4	Umbilical interfaces	(2)		X	X	X	X		
47.5	Computer & peripheral equipment	(2)		X	X	X	X		
47.6	Recording/timing unit	(2)		X	X	X	X		
47.7	Operator console	(1)		X	X	X	X		
48.0	Remove from assay stand & transfer to int. test site	(1)			X				
49.0	Mate cargo & integration test GSE	(1)			X	X	X		GSE simulator Vs IVE trade study
50.0	Pre-power interface verification tests	(1)		See remarks	X		X		If accomplished at User site, demate, ship, remate and reverify at launch site
50.1	Bus isolation test	(1)			X		X		
50.2	Switch position check	(1)			X		X		
50.3	Test readiness check	(1)			X		X		
51.0	Power-up interface verification test	(2),(3)			X	X	X		
51.1	Electrical power distribution test	(1)			X	X	X		
51.2	Verify caution & warning circuitry	(2)			X	X	X		
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

C-74

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
51.3	Computer self checks	(1)	Launch site		X	X	X		If accomplished at User site, demate, ship, remate and reverify at launch site
51.4	Verify data management system command/control & peripheral equipment	(2)			X	X	X		
51.5	Checkout auxiliary equipment (intercom, lighting, etc.)	(1)			X	X	X		
51.6	C/O ground data base compatibility	(3)			X	X	X		
51.7	Checkout signal distribution	(1)			X	X	X		
52.0	Functional interface verification	(2)			X	X	X		
52.1	C/O support systems & experiment interfaces	(1)			XX	X	X		
52.2	Checkout command & control via IMS	(2)			X	X	X		
52.3	Checkout emergency backup modes	(2)			X	X	X		
53.0	Final calibration of experiments	(1)			X				
54.0	Data review	(2)			X				Can be accomplished anywhere
55.0	Final closeout of modules/experiments	(1)			X				
55.1	Disconnect GSE	(1)			X				
55.2	Load non-hazardous supplies	(1)			X				
55.3	Closeout hatches & access doors	(1)			X				
56.0	Emissivity test of external surfaces	(1)			X				
57.0	Remove payload station panels	(1)			X				
58.0	Prepare & transfer P.S. panels to OFF	(1)			X				
59.0	Pressure decay leak test of habitable compartment	(1)			X				

* (1) ORBITER I/F NOT REQUIRED

(2) ORBITER I/F KNOWLEDGE REQUIRED

(3) DIRECT ORBITER FUNCTION SIMULATED

(4) DIRECT ORBITER I/F

Table C.3 (Cont) MODULE WITH PALLET (SPACELAB)

BLOCK No.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
60.0	Demate cargo from integration stand	(1)	Launch site		X				
61.0	Secure integration test GSE	(1)			X				
62.0	Perform weight & balance operations	(1)			X			X	
63.0	Prepare & transfer to OPT	(1)			X			X	Special handling equipment
64.0	Prepare cargo for installation in orbiter	(1)			X				
64.1	Install in workstand	(1)			X				
64.2	Service with non-hazardous fluids	(1)			X				
64.3	Install flight batteries and chargers	(1)			X				
64.4	Install lifting devices	(1)			X				
65.0	Install payload station panels in orbiter	(4)			X				
66.0	Perform cargo to orbiter mating operations	(4)			X				
67.0	Orbiter/cargo interface verification	(4)			X				Orbiter responsibility
67.1	Plugs out continuity check	(1)			X				
67.2	Connect & verify electrical cables	(4)			X				
67.3	Connect & verify fluid fittings	(4)			X				
67.4	Connect & verify all support umbilicals	(4)			X				
68.0	Install tunnel	(4)			X				
69.0	Perform orbiter integration test (cargo oriented OPT)	(4)			X				

* (1) ORBITER I/F NOT REQUIRED

(2) ORBITER I/F KNOWLEDGE REQUIRED

(3) DIRECT ORBITER FUNCTION SIMULATED

(4) DIRECT ORBITER I/F

C-76

BLOCK NO.	DESCRIPTION	INTERFACES				CH*KOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE TIM.	IVE		
70.0	Verify orbiter/cargo EMC/RFI	(4)	Launch site		X				Orbiter responsibility
70.1	Monitor during OIT functional tests	(4)			X				↓
71.0	Perform final spacelab OPE operations	(4)			X				Use OPE equipment
71.1	Install ordnance in locations not accessible at pad	(4)			X				↓
71.2	Install all panels and covers	(1)			X				
71.3	Leak-check tunnel pressure decay	(4)			X				
71.4	Leak check tunnel hatch	(1)			X				
71.5	Leak check spacelab interface	(4)			X				
71.6	Orbiter closeout	(4)			X				↓
72.0	Review all processing & test data	(2)			X				
73.0	Transfer to VAB	(4)			X				Orbiter responsibility
74.0	Conduct orbiter VAB operations	NA			X				
74.1	Shuttle interface test	NA			X				
74.2	Install & connect ordnance	NA			X				
74.3	Prepare for roll out	NA			X				
75.0	Transfer to launch pad	NA			X				
76.0	Platform orbiter launch readiness verif. ops.	NA			X				
77.0	Payload servicing	(4)			X				As required
78.0	Closeout orbiter & secure GSE	NA			X				

* (1) ORBITER I/F NOT REQUIRED

(2) ORBITER I/F KNOWLEDGE REQUIRED

(3) DIRECT ORBITER FUNCTION SIMULATED

(4) DIRECT ORBITER I/F

Table C.3 (Cont) MODULE WITH PALLETS (SPACELAB)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GPS SIM.	IVE		
79.0	Launch operations	NA	Launch site		X				
79.1	Clear pad	NA			X				
79.2	Stand by	NA			X				
79.3	Countdown	NA			X				
79.4	Liftoff	NA			X				
80.0	Landing operations	NA			X				
80.1	De-service	NA			X				
80.2	Safing operations	NA			X				
80.3	Open payload doors	NA			X				
81.0	Disconnect tunnel from orbiter	NA			X				
82.0	Remove cargo	(4)			X				
83.0	Remove P/L station panels & utility harness	(4)			X				
84.0	Move to O & C facility	(1)			X				
85.0	Move to O & C facility	(1)			X				
86.0	Perform receiving inspection	(1)			X				
87.0	Install in spacelab workstand	(1)			X				
88.0	Perform preliminary interior inspection	(1)			X				
89.0	Perform post-flight subsystem checkout	(2)			X				
90.0	Remove EM/SM shells & FS equipment & additional rack sets and floors	(1)			X				
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

Table C.3 (Cont). MODULE WITH PALLETS (SPACELAB)

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GS% SIM.	IVE		
91.0	Remove pallets/experiments	(1)	Launch site		X				
92.0	Remove racks/experiments	(1)			X				
93.0	Demate aft bulkhead	(1)			X				
94.0	Demate tunnel	(1)			X				
95.0	Demate experiments from pallet	(1)			X				
96.0	Demate experiments from racks	(1)			X				
97.0	Service aft bulkhead as required	(1)			X				
98.0	Service tunnel as required	(1)			X				
99.0	Return experiments to experimenter	(1)		X					
100.0	Return experiments to experimenter	(1)		X					
101.0	Refurbish pallets	(1)			X				
102.0	Refurbish racks	(1)			X				
103.0	Store aft bulkhead	(1)			X				
104.0	Store tunnel	(1)			X				
105.0	Transfer pallets	(1)			X				
106.0	Transfer racks	(1)			X				
107.0	Transfer aft bulkhead	(1)			X				
108.0	Transfer tunnel	(1)			X				
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									




Figure C-4 Large Space Telescope FFED






Figure C-4 Large Space Telescope FFBD (Cont)

ORIGINAL PAGE IS
OF POOR QUALITY



- (1) ORBITER I/F NOT REQUIRED
- (2) ORBITER I/F KNOWLEDGE REQUIRED
- (3) DIRECT ORBITER FUNCTIONS SIMULATED
- (4) DIRECT ORBITER I/F


Figure C-4, Large Space Telescope FFBD (Cont)



- (1) ORBITER I/F NOT REQUIRED
(2) ORBITER I/F KNOWLEDGE REQUIRED
(3) DIRECT ORBITER FUNCTIONS SIMULATED
(4) DIRECT ORBITER I/F

Figure C-4 Large Space Telescope FFBD (Cont)

ORIGINAL PAGE IS
OF POOR QUALITY



- (1) ORBITER I/F NOT REQUIRED
(2) ORBITER I/F KNOWLEDGE REQUIRED
(3) DIRECT ORBITER FUNCTIONS SIMULATED
(4) DIRECT ORBITER I/F

Figure C-4 Large Space Telescope FFBD (Cont)

ORIGINAL PAGE IS
OF POOR QUALITY




Figure C-4 Large Space Telescope FFBD (Cont)




Figure C-4 Large Space Telescope FFBD (Cont.)




Figure C-4 Large Space Telescope FFBD (Cont)

- (1) ORBITER I/F NOT REQUIRED
- (2) ORBITER I/F KNOWLEDGE REQUIRED
- (3) DIRECT ORBITER FUNCTIONS SIMULATED
- (4) DIRECT ORBITER I/F

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.4 LST INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	LIVE		
1.0	Service system module (SSM) buildup	(2)	User	X					Various sources
1.1	Data management subsystem assembly	(2)		X					
1.1.1	Data interface units	(2)		X					
1.1.2	Computer interface unit	(2)		X					
1.1.3	Data exchange unit	(2)		X					
1.1.4	Auxiliary memory unit	(2)		X					
1.1.5	Command decoder	(1)		X					
1.1.6	Power switch & decoder	(1)		X					
1.1.7	Central processor	(2)		X					
1.1.8	Input/output processor	(2)		X					
1.1.9	Main memory	(1)		X					
1.1.10	Computer power converter	(1)		X					
1.1.11	Oscillator	(1)		X					
1.1.12	Tape recorders	(1)		X					
1.2	Instrumentation & communication subsystem assy.	(2)		X					
1.2.1	Transponder	(1)		X					
1.2.2	Duplexers	(1)		X					
1.2.3	Circulator	(1)		X					
1.2.4	Antenna electronics	(2)		X					
<div> <div>1 ORBITER I/F NOT REQUIRED</div> <div>2 ORBITER I/F KNOWLEDGE REQUIRED</div> <div>3 DIRECT ORBITER FUNCTION "SIMULATE"</div> <div>4 DIRECT ORBITER I/F</div> </div>									

Table C.4 (Cont) LST INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
1.2.5	Antenna drive and boom	(2)	User	X					Various sources
1.2.6	Omni antenna	(2)		X					
1.2.7	Power amplifier	(1)		X					
1.2.8	RF switches	(1)		X					
1.2.9	High gain antenna	(2)		X					
1.3	Pointing control subsystem assembly	(2)		X					
1.3.1	Fixed star tracker	(2)		X					
1.3.2	Fine gyro assembly	(2)		X					
1.3.3	Magnetic torquer	(1)		X					
1.3.4	Reaction wheels	(1)		X					
1.3.5	Retrieval electronics	(2)		X					
1.3.6	Coarse sun sensor	(1)		X					
1.3.7	Magnetometer	(1)		X					
1.3.8	Retrieval rate gyros	(2)		X					
1.4	Electrical power subsystem assembly	(2)		X					
1.4.1	Power control & distribution	(2)		X					
1.4.2	Solar array electrical interface	(2)		X					
1.4.3	Umbilical & cabling	(2)		X					
1.4.4	Solar array drive assembly	(2)		X					
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.4 (Cont) 1ST INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITF ORIENTED	GRG SIM.	IVE		
1.4.5	Batteries	(1)	User.	X					Various sources
1.4.6	Charge controller	(1)		X					
1.4.7	Solar array wing	(2)		X					
1.4.8	Solar array deploy mechanism	(2)		X					
1.5	Structural subsystem	(2)		X					
1.5.1	Structural subsystem assembly	(1)		X					
1.5.1.1	Fittings	(1)		X					
1.5.1.2	Latches	(1)		X					
1.5.1.3	Aperture doors	(1)		X					
1.5.1.4	Panels	(1)		X					
1.5.1.5	Insulation	(1)		X					
1.5.2	Static load test of struct. components & fitt.	(1)		X					
1.5.3	Install mass simulators	(1)		X		X			
1.5.3.1	Optical telescope assy (OTA) mass simulator	(1)		X		X			
1.5.3.2	Scientific instrument module mass simulator	(1)		X		X			
2.0	Subsystem acceptance	(1)		X					
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

Table C.6 (Cont). LST INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	G98 SIM.	IVE		
3.0	Install subsystems on SSM structure	(1)	User	X					
4.0	Perform SSM dynamic test	(1)		X				X	
4.1	Vibration transmissibility	(1)		X				X	
4.2	Modal analyses	(1)		X					
5.0	Modify SSM to flight configuration	(1)		X					
5.1	Remove mass simulators	(1)		X					
5.2	Inspect & replace flight hardware as required	(1)		X					
5.3	Install additional flight hardware as required	(1)		X					
6.0	System I/F simulator: OPA & SI are electrically simulated	(1)		X		X			
6.1	System simulator readiness tests	(1)		X		X		X	
6.1.1	Environmental tests	(1)		X				X	
6.1.2	Functional tests	(1)		X					
7.0	Mate SSM & system simulator	(1)		X		X			
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

Table C.6 (Cont) LST INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
8.0	Perform initial SSM functional tests	(1)	User	X	X	X	X		Either site
8.1	Electrical performance	(1)		X	X	X	X		
8.2	Mechanical performance	(1)		X	X	X	X		
8.3	Software checkout	(1)		X	X	X	X		
8.4	Test procedures checkout	(1)		X	X	X	X		
8.5	OTA/SI interfaces	(1)		X	X	X	X		
9.0	Perform SSM functional tests	(2)		X	X	X	X		
9.1	DMS functional test	(2)		X	X	X	X		
9.2	ICS functional test	(2)		X	X	X	X		
9.3	ICS functional test	(2)		X	X	X	X		
9.4	EPS functional test	(2)		X	X	X	X		
10.0	Receive OTA at user site	(1)		X					
10.1	OTA receiving inspection	(1)		X					
11.0	Receive 4 scientific instr. at user site	(1)		X					
11.1	SI receiving inspection	(1)		X					
<div> <div> (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED </div> <div> (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F </div> </div>									

Table C.4 (Cont) LST INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH STTP ORIENTED	GSE SIM.	IVE		
12.0	Remove OTA & SI simulators	(1)	User	X	X				Either site
13.0	LST assembly operations	(1)		X	X				
13.1	Mate OTA, SI & GSM	(1)		X	X				
13.2	Verify electrical & mechanical interfaces	(1)		X	X				
13.3	Verify alignment	(1)		X	X				
13.4	Perform bus isolation tests	(1)		X	X				
13.5	Verify grounding	(1)		X	X				
14.0	LST functional interface test	(2)		X	X	X	X		Trade study
14.1	Verify command interface	(2)		X	X	X	X		
14.2	Verify telemetry interface	(2)		X	X	X	X		
14.3	Verify timing signal interface	(2)		X	X	X	X		
14.4	Verify grounding interface	(1)		X	X	X	X		
14.5	Verify electrical power interface	(2)		X	X	X	X		
15.0	LST mission simulation	(2)		X	X	X	X		
15.1	Launch conditioning	(2)		X	X	X	X		
15.2	Ascent	(2)		X	X	X	X		
15.3	Pre-deployment	(2)		X	X	X	X		
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

Table C.4 (Cont) LST INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	OSF SIM.	IVE		
15.4	Post-deployment	(2)	User	X	X	X	X		Trade study
15.5	Orbit operation	(2)		X	X	X	X		
15.6	Retrieval	(2)		X	X	X	X		
15.7	Reentry	(2)		X	X	X	X		
15.8	Recovery	(2)		X	X	X	X		
16.0	LST to data center interface compatibility	(2)		X	X	X	X		
16.1	BMC	(2)		X	X	X	X		
16.2	Software validation	(1)		X	X	X	X		
16.3	Capability to transmit & receive commands & data	(2)		X	X	X	X		
17.0	Acoustic test	(1)		X	X			X	
17.1	Post-acoustic functional test	(2)		X	X	X	X		
17.1.1	DMS functional test	(2)		X	X	X	X		
17.1.2	IGS functional test	(2)		X	X	X	X		
17.1.3	FCS functional test	(2)		X	X	X	X		
17.1.4	EPS functional test	(2)		X	X	X	X		
17.1.5	OTA functional test	(2)		X	X	X	X		
17.1.6	SI functional test	(2)		X	X	X	X		
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

Table C.4 (Cont) LST INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GR% SIM.	IVE		
18.0	Thermal vac/thermal balance test	(2)	User	X	X			X	Trade study
18.1	Simulate orbital operational conditions	(2)		X	X			X	
18.2	Operate all functional modes	(2)		X	X	X	X	X	
18.3	Post-test functional verification	(2)		X	X	X	X		
19.0	Configure LST for final operations & tests	(2)		X	X				Either site
19.1	Remove test instrumentation	(1)		X	X				
19.2	Configure for flight	(2)		X	X				
19.3	Reflectivity/emissivity measurements	(1)		X	X				
20.0	Weight and balance test	(1)		X	X			X	
21.0	Prepare vertical or optional horizontal integration stand	(1)		X	X		X	X	Assuming IVE is adaptable to asgy.
22.0	Install LST in integration stand	(2)		X	X				Either site
23.0	Perform LST/orbiter compatibility tests	(3)		X	X	X	X		Trade study
23.1	Verify mechanical interface	(3)		X	X	X	X		
23.2	Verify electrical interface	(3)		X	X	X	X		
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

Table C.4 (Cont) LST INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	OPF SIM.	IVE		
23.3	Launch readiness/conditioning sequences	(3)	User	X	X	X	X		Trade study
23.4	Pre-deployment/post-deployment sequences	(3)		X	X	X	X		
23.5	Retrieval/recovery sequences	(3)		X	X	X	X		
24.0	Package & ship SSE to Launch site	(1)		X					
24.1	Umbilical cables	(1)		X					
24.2	LST MS panel	(1)		X					
24.3	Payload purge system	(1)		X					
24.4	TTP equipment	(1)		X					
24.5	EVA support equipment	(1)		X					
25.0	SSE arrival at Launch site	(1)	Launch site		X				
26.0	Transfer SSE to receiving facility	(1)			X				
26.1	SSE receiving inspection	(1)			X				
27.0	Transfer SSE to OPF	(1)			X			X	
27.1	Install SSE in orbiter (OPF)	(4)			X			X	
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE 1
DE POOR QUALITY

Table C.4 (Cont). LST INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	G99 SIM.	IVE		
28.0	Clossout, package & ship to Launch site	(1)	User	X					
28.1	Install protective covers	(1)	↓	X					
28.2	Service with liquid helium	(1)	↓	X					
29.0	LST arrival at Launch site	(1)	Launch site		X				
30.0	Transfer Lst to receiving facility	(1)			X			X	
31.0	Perform LST receiving inspection	(1)			X			X	
32.0	Install payload in canister	(1)			X				
32.1	Erect payload canister to vertical position	(1)			X				
33.0	Transfer Payload canister to PCR at pad	(1)			X			X	
34.0	Perform orbiter/payload interface verification and servicing	(1),(2)		X	X	X	X		Both sites; trade study
34.1	Charge flight batteries	(1)		X	X				
34.2	Service with liquid helium	(1)		X	X				
34.3	Orbiter/payload interface verification	(2)	↓	X	X	X	X		↓
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.4 (Cont). LST INTERFACE CHECKOUT MATRIX

[illegible]





Figure C-5 Mariner Jupiter Orbiter/IUS

ORIGINAL PAGE IS
OF POOR QUALITY



- (1) ORBITER I/F NOT REQUIRED
- (2) ORBITER I/F KNOWLEDGE REQUIRED
- (3) DIRECT ORBITER FUNCTIONS SIMULATED
- (4) DIRECT ORBITER I/F

Figure C-5 Mariner Jupiter Orbiter/IUS (Cont)





Figure C-5 Mariner Jupiter Orbiter/IUS (Cont)

- (1) ORBITER I/F NOT REQUIRED
 (2) ORBITER I/F KNOWLEDGE REQUIRED
 (3) DIRECT ORBITER FUNCTIONS SIMULATED
 (4) DIRECT ORBITER I/F



- (1) ORBITER I/F NOT REQUIRED
 (2) ORBITER I/F KNOWLEDGE REQUIRED
 (3) DIRECT ORBITER FUNCTIONS SIMULATED
 (4) DIRECT ORBITER I/F

Figure C-5 Mariner Jupiter Orbiter/IUS (Cont)




Figure C-5 Mariner Jupiter Orbiter/IUS (Cont)

ORIGINAL PAGE IS
OF POOR QUALITY

C-103




Figure C-5 Mariner Jupiter Orbiter/IUS (Cont)




Figure C-5 Mariner Jupiter Orbiter/IUS (Cont)




Figure C-5 Mariner Jupiter Orbiter/IUS (Cont)





Figure C-5 Mariner Jupiter Orbiter/IUS (Cont)


ORIGINAL PAGE IS
OF POOR QUALITY

C-107



- | |
|--|
| (1) ORBITER I/F NOT REQUIRED
(2) ORBITER I/F KNOWLEDGE REQUIRED
(3) DIRECT ORBITER FUNCTIONS SIMULATED
(4) DIRECT ORBITER I/F |
|--|


Figure C-5 Mariner Jupiter Orbiter/IUS (Cont)



C-10B


- (1) ORBITER I/F NOT REQUIRED
- (2) ORBITER I/F KNOWLEDGE REQUIRED
- (3) DIRECT ORBITER FUNCTIONS SIMULATED
- (4) DIRECT ORBITER I/F

Figure C-5 Mariner Jupiter Orbiter/IUS (Cont)




- (1) ORBITER I/F NOT REQUIRED
- (2) ORBITER I/F KNOWLEDGE REQUIRED
- (3) DIRECT ORBITER FUNCTIONS SIMULATED
- (4) DIRECT ORBITER I/F

Figure C-5 Mariner Jupiter Orbiter/XUS (Cont)




- (1) ORBITER I/F NOT REQUIRED
 (2) ORBITER I/F KNOWLEDGE REQUIRED
 (3) DIRECT ORBITER FUNCTIONS SIMULATED
 (4) DIRECT ORBITER I/F

Figure C-5 Mariner Jupiter Orbiter/IUS (Cont)



- | |
|--|
| (1) ORBITER I/F NOT REQUIRED
(2) ORBITER I/F KNOWLEDGE REQUIRED
(3) DIRECT ORBITER FUNCTIONS SIMULATED
(4) DIRECT ORBITER I/F |
|--|

Figure C-5 Mariner Jupiter Orbiter/IUS (Cont)



- (1) ORBITER I/F NOT REQUIRED
- (2) ORBITER I/F KNOWLEDGE REQUIRED
- (3) DIRECT ORBITER FUNCTIONS SIMULATED
- (4) DIRECT ORBITER I/F

Figure C-5 Mariner Jupiter Orbiter/IUS (Cont)

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.5 MJO/IUS INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	G99 SIM.	IVE		
1.0	Develop & verify experiments & related equipment	(a)	User	X					Various sources
1.1	Cosmic ray detector	(2)		X					
1.2	Planetary radio astronomy	(2)		X					
1.3	Ultraviolet photometer	(2)		X					
1.4	Low energy charged particle detector	(2)		X					
1.5	Photopolarimeter	(2)		X					
1.6	Plasma detector	(2)		X					
1.7	Ultraviolet spectrometer	(2)		X					
1.8	Magnetometer	(2)		X					
1.9	Imaging science 800x800 CCD sensor	(2)		X					
1.10	IR interferometer spectrometer	(2)		X					
2.0	Receive & inject experiments & related equip.	(1)		X					
2.1	2.1 through 2.10 experiments same as 1.1 through 1.10 are acceptance tested	(1)		X					
3.0	Develop & verify support subsystems	(2)		X					
3.1	IT & C	(2)		X					
3.2	Electrical	(2)		X					
3.3	Environmental control	(1)		X					
3.4	Guidance, navigation & stabilization	(1)		X					
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

Table C.5 (Cont) MJO/IUE INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITF ORIENTED	GSE SIM.	IVE		
3.5	Attitude control	(1)	User	X					Various sources
3.6	Propulsion	(1)		X					
4.0	Receive & inspect support subsystems	(1)		X					
4.1	4.1 through 4.6 subsystems same as 3.1 through 3.6 are acceptance tested	(1)		X					
5.0	Assemble & inspect spacecraft structure	(2)		X					
6.0	Assemble spacecraft	(1)		X	X				Either site; trade study
7.0	Prepare & calibrate test GSE	(1)		X	X				
8.0	Mate spacecraft & test GSE	(1)		X	X				
9.0	Verify mechanical interfaces	(2)		X	X				
9.1	Mechanical attachment of experim. & subsystems	(1)		X	X				
9.2	Location of mounting points	(2)		X	X				
9.3	Clearances	(2)		X	X				
9.4	Umbilical locations	(2)		X	X				
9.5	Alignment	(1)		X	X				
10.0	Verify electrical interfaces	(1)		X	X				
10.1	Grounding	(1)		X	X				
10.2	Bug isolation	(1)		X	X				
10.3	Continuity	(1)		X	X				
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.5 (Cont) MLO/IUS

INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
11.0	Verify fluid interfaces	(1)	User	X	X				Either site: trade study
11.1	Leakcheck fluid fittings	(1)		X	X				
11.2	Leakcheck fluid systems	(1)		X	X				
12.0	Perform system level functional tests	(2)		X	X	X	X		
12.1	Power distribution & electrical load	(2)		X	X	X	X		
12.2	Caution & warning operation	(2)		X	X	X	X		
12.3	Guidance, navigation & stabilization	(2)		X	X	X	X		
12.4	Attitude control	(2)		X	X	X	X		
12.5	Telemetry	(2)		X	X	X	X		
12.6	Tracking	(2)		X	X	X	X		
12.7	Command RFS	(2)		X	X	X	X		
12.8	Tape recorder	(2)		X	X	X	X		
12.9	Antenna	(2)		X	X	X	X		
12.10	Pyrosystems	(1)		X	X	X	X		
12.11	Typical payload experiments (10 total)	(1)		X	X	X	X		
12.21	EMC	(1)		X	X	X	X		
13.0	Transfer spacecraft to thermo/vac facility	(1)		X	X			X	
14.0	Prepare for thermo/vac tests	(1)		X	X			X	
14.1	Add thermal blankets	(1)		X	X			X	
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

Table C.5 (Cont) MJO/IUS

INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
15.0	Perform system continuity check	(1)	User	X	X				
15.1	15.1 through 15.20 same as 12.1 through 12.20 functional check	(1)		X	X				
16.0	Prepare & calibrate thermo/vac facility GSE	(1)		X	X			X	
17.0	Mate thermo/vac GSE to spacecraft	(1)		X	X			X	
18.0	System level thermo/vac tests	(2)		X	X	X	X		
18.1	Simulate orbit operational conditions	(2)		X	X	X	X		
18.2	Operate all functional modes	(2)		X	X	X	X		
18.3	Post test functional verification	(1)		X	X	X	X		
19.0	Data review	(1)		X	X				Alternate site
20.0	Transfer S/C to vibr/acoustic facility	(1)		X	X			X	
21.0	Prepare & calibrate vibro/acc. facility GSE	(1)		X	X			X	
22.0	Mate vibro/acc facility GSE to spacecraft	(1)		X	X			X	
23.0	System vibro/acoustic tests	(1)		X	X			X	
23.1	Random/acoustic vibration tests	(1)		X	X			X	
23.2	Functional check	(1)		X	X			X	
23.3	Pyrocheck	(1)		X	X			X	
24.0	Post vibro/acc system continuity check	(1)		X	X			X	
24.1	24.1 through 24.2 Same as 12.1 through 12.20 functional check	(1)							
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.5 (Cont) MJO/TUB INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
25.0	Transfer to system checkout facility	(1)	User	X	X				
26.0	Prepare & calibrate unique GSE for RTG	(1)		X	X	X			Unique GSE
27.0	Mate unique GSE to spacecraft	(1)		X	X	X			↓
28.0	Perform RTG simulation test	(1)		X	X	X			
29.0	Systems functional check	(1)		X	X	X	X		
29.1	29.1 through 29.20 same as 12.1 through 12.20 functional check	(1)		X	X	X	X		
30.0	Prepare unique calibration GSE	(1)		X	X				Unique GSE
31.0	Mate unique calibration GSE to spacecraft	(1)		X	X				↓
32.0	Calibrate experiments	(1)		X	X				↓
32.1	32.1 through 32.10 same as 1.1 through 1.10	(1)		X	X				
33.0	Perform post environmental insp. & funct. check	(2)		X	X	X	X		
33.1	33.1 through 33.20 same as 12.1 through 12.20	(2)		X	X	X	X		
34.0	Refurbish equipment as necessary	(1)		X	X				
35.0	Prepare for mission sim. tests with experiments	(2)		X	X				
36.0	Perform mission sim. tests with experiments	(2)		X	X	X	X		Either site: trade study
36.1	Launch conditions	(2)		X	X	X	X		↓
36.2	Ascent	(2)		X	X	X	X		
36.3	Predeployment	(2)		X	X	X	X		
36.4	Post deployment	(2)	↓	X	X	X	X		↓
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

Table C.5 (Cont) MJO/IUS

INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITT ORIENTED	GSE SIM.	IVE		
36.5	Orbit operations	(2)	User	X	X	X	X		Either site: trade study
37.0	Data review	(1)		X	X				Alternate site
38.0	Perform mechanisms deployment tests	(1)		X	X	X			
39.0	Transfer to WT/CG facility	(1)		X	X				
40.0	Prepare & calibrate WT/CG facility GSE	(1)		X	X			X	
41.0	Install spacecraft in WT/CG facility	(1)		X	X			X	
42.0	Determine WT/CG	(1)		X	X			X	
43.0	Transfer to EMC/RFI facility	(1)		X	X				
44.0	Prepare EMC/RFI facility GSE	(1)		X	X				
45.0	Install spacecraft in EMC/RFI facility	(1)		X	X				
46.0	Perform EMC/RFI tests	(1)		X	X				
46.1	46.1 through 46.20 same as 12.1 through 12.20	(1)		X	X				
47.0	Transfer to spin facility	(1)		X	X				
48.0	Prepare & calibrate spin facility GSE	(1)		X	X			X	
49.0	Install spacecraft in spin facility, (spacecraft to be spin stabilized in orbit)	(1)		X	X			X	
50.0	Perform spin tests	(1)		X	X			X	
51.0	Transfer to clean facility	(1)		X	X				
52.0	Prepare clean facility	(1)		X	X			X	
53.0	Clean spacecraft & prepare for shipment	(1)		X	X				
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

C-119

Table C.5 (Cont)

INTERFACE CHECKOUT MATRIX

* 1 ORRITER I/F NOT REQUIRED

2 ORBITER I/F KNOWLEDGE REQUIRED

3 DIRECT ORBITER
FUNCTION SIMULATED

4 DIRECT OFFITER I/F

Table C.5 (Cont) MJO/IUS

INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	OPS SIM.	IVE		
69.0	Subsystem checkout	(2)	Launch site		X	X	X		Trade study
69.1	Power	(2)			X	X	X		
69.2	Caution & warning	(2)			X	X	X		
69.3	Guidance & navigation	(2)			X	X	X		
69.4	Communications	(2)			X	X	X		
69.5	Reaction control system (RCS)	(2)			X	X	X		
69.6	Thrust vector control (TVC)	(2)			X	X	X		
69.7	Telemetry (TLM)	(2)			X	X	X		
70.0	Combined IUS system tests	(2)			X	X	X		
70.1	70.1 through 70.7 same as 69.1 through 69.7	(2)			X	X	X		
71.0	Data review	(2)			X				
71.1	Review data	(1)			X				
71.2	Retest if necessary	(2)			X				
72.0	Prepare batteries for installation	(1)			X				
73.0	Install batteries	(1)			X				
73.1	Electronic battery	(1)			X				
73.2	Utility battery	(1)			X				
74.0	Install thermal blankets	(1)			X				
75.0	Mate S/C to IUS	(1)			X		X		IVE may be used for mating
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

GENERAL PAGE IS
OF POOR QUALITY

Table C.5 (Cont). MVO/IUS INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
76.0	Install cargo in checkout assembly	(3)	Launch site		X	X	X		Could be IVE or assembly structure
77.0	Mechanical interface and envelope check	(3)			X		X		
77.1	Attach points	(3)			X		X		
77.2	Bay door clearance	(3)			X		X		
77.3	Latches clearance	(3)			X		X		
77.4	Door actuators	(3)			X		X		
77.5	RMS support	(3)			X		X		
77.6	Electrical connectors	(3)			X		X		
77.7	Fluid connectors	(3)			X		X		
78.0	Fluid interface check	(3)			X	X	X		
78.1	Leakage check	(3)			X	X	X		
78.2	Pressure test	(3)			X	X	X		
79.0	RVG coolant loop check	(3)			X		X		IVE cooling system will accommodate RVG
79.1	Leakage check	(3)			X		X		
79.2	Pressure test	(3)			X		X		
79.3	Flow check	(3)			X		X		
80.0	Electrical interface check	(3)			X				
80.1	Bus isolation	(3)			X				
80.2	Grounding check	(3)			X				
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

Table C.5 (Cont) MJO/IUS

INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
81.0	Determine power distribution	(3)	Launch site		X	X	X		Either one; trade study
81.1	Voltage variation	(3)			X	X	X		
81.2	Transients	(3)			X	X	X		
81.3	Ripple	(3)			X	X	X		
82.0	Verify electrical system functional interface	(3)			X	X	X		
82.1	C&W system	(3)			X	X	X		
82.2	Data system	(3)			X	X	X		
82.3	Command & control system	(3)			X	X	X		
83.0	Calibrate experiments & FEE	(3)			X	X	X		Unique GSE
83.1	83.1 through 83.10 same as 1.1 through 1.10	(3)			X	X	X		
84.0	Load & verify flight software	(3)			X	X	X		Either one; trade study
84.1	Signal generation	(3)			X	X	X		
84.2	Real time monitoring	(3)			X	X	X		
85.0	Integrated support system/experiment verific.	(3)			X	X	X		
85.1	85.1 through 85.16 same as 1.1 through 1.10 and 3.1 through 3.6	(3)			X	X	X		
86.0	Operational tests in orbiter environment	(3)			X	X	X		
87.0	Perform EMI/RFI tests simultaneously with operational tests	(3)			X	X	X		
88.0	Verify compatibility with tracking stations	(3)			X	X	X		Unique equipment/facility
89.0	Transfer to WT/BAL facility	(1)			X				
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									

ORIGINAL PAGE IS
OF POOR QUALITY

Table C.5 (Cont) MJO/IUS INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
89.1	Prepare for transfer	(1)	Launch site		X				
89.2	Transfer	(1)			X				
89.3	Receiving inspection	(1)			X				
90.0	Prepare & calibrate WT/BAL facility GSE	(1)			X				
91.0	Install cargo to WT/BAL GSE	(1)			X				
92.0	Perform WT/BAL test	(2)			X				
93.0	Transfer cargo to pad	(1)			X				
94.0	Install cargo in PCR	(2)			X			X	Specilined handling equipment
95.0	Extend cargo changeout room	(4)			X			X	
95.1	Inflate PCR/orbiter seal	(4)			X			X	
95.2	Purge interstitial area	(4)			X			X	
95.3	Open PCR door	(1)			X			X	
96.0	Install RTG to cargo	(4)			X				Specialized handling equipment
97.0	Extend cargo into payload bay	(4)			X				
98.0	Mate cargo to orbiter	(4)			X				
98.1	Mechanical	(4)			X				
98.2	Electrical connectors	(4)			X				
98.3	Fluid connectors	(4)			X				
99.0	Cargo/orbiter interface verification	(4)			X				
* (1) ORBITER I/F NOT REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (2) ORBITER I/F KNOWLEDGE REQUIRED (4) DIRECT ORBITER I/F									

Table C.5 (Cont) MJO/IUS

INTERFACE CHECKOUT MATRIX

BLOCK NO.	DESCRIPTION	INTERFACES				CHECKOUT/TEST EQUIPMENT		SPECIAL FACILITY	REMARKS
		* I/F KNOWLEDGE	BASELINE LOCATION	OPTION 1 USER ORIENTED	OPTION 2 LAUNCH SITE ORIENTED	GSE SIM.	IVE		
99.1	Plugs out electrical continuity	(h)	Launch site		X				
99.2	Connect & verify umbilicals and fluid lines	(h)			X				
99.3	Install and verify mechanical latches and retention devices	(h)			X				
100.0	Cargo power on	(h)			X				
101.0	Cargo Launch Readiness Verification (LRV)	(h)			X				
102.0	Disconnect payload ground handling mechanisms (RGHM) from cargo	(h)			X				
102.1	Secure RGHM in ECR	(h)			X				
103.0	Closeout bay doors	(h)			X				
103.1	Retract Rendezvous radar (R/R) antennas	(h)			X				
103.2	Retract RMS	(h)			X				
104.0	Cabin closeout	(h)			X				
105.0	Clear pad	(h)			X				
106.0	Cargo services (as required)	(h)			X				
107.0	Retract cargo changeout room	(h)			X				
108.0	Launch operations	(h)			X				
* (1) ORBITER I/F NOT REQUIRED (2) ORBITER I/F KNOWLEDGE REQUIRED (3) DIRECT ORBITER FUNCTION SIMULATED (4) DIRECT ORBITER I/F									